

**WaterSMART: Water and Energy Efficiency Grants for  
Fiscal Year 2019 – Funding Group 1**

**Cameron County Irrigation District No. 2**

**Conversion of Lateral 8 from Open Canal to a Pipeline**

Submitted By:  
Sonia Lambert, General Manager  
26041 FM 510  
PO Box 687  
San Benito, Texas 78586  
Phone: (956) 399-2484  
Fax: (956) 399-4721  
ccid2@swbell.net

March 2019

PREPARED BY:  
Vicente Mendez, PE, RPLS, Project Manager  
Anne Whitko, Assistant Project Manager



**AMBIOTEC  
GROUP**

5420 PAREDES LINE ROAD  
BROWNSVILLE, TEXAS 78526  
PHONE (956) 548-9333  
FAX (956) 548-9399

[vmendez@ambiotec.com](mailto:vmendez@ambiotec.com) / [awhitko@ambiotec.com](mailto:awhitko@ambiotec.com)

TBPE Firm No.: F-4126  
TBPLS Reg. No.: 10005300



MAR 18 '19 AM 10:21

# Table of Contents

SF-424 Application for Federal Assistance

SF-424C Budget Form

SF-424D Assurances

SF-LLL Disclosure of Lobbying Activities

Title Page

Table of Contents

List of Figures

List of Tables

List of Appendices

Technical Proposal .....	1
Executive Summary .....	1
Background Data.....	1
Project Location .....	3
Project Description.....	3
E.1 Evaluation Criteria .....	4
E.1.1 Evaluation Criterion A: Quantifiable Water Savings .....	4
E.1.2 Evaluation Criterion B: Water Supply Reliability.....	6
E.1.3 Evaluation Criterion C: Implementing Hydropower .....	7
E.1.4 Evaluation Criterion D: Complementing On-Farm Irrigation Improvements .....	7
E.1.5 Evaluation Criterion E: Department of the Interior Priorities .....	8
E.1.6 Evaluation Criterion F: Implementation and Results .....	8
E.1.7 Evaluation Criterion G: Nexus to Reclamation Project Activities.....	10
E.1.8 Evaluation Criterion H: Additional Non-Federal Funding.....	11
Project Budget.....	11
Environmental and Cultural Resources Compliance.....	14
Required Permits and Approvals.....	15
Requirements for Agricultural Operations under P.L. 111-11, Section 9504(a)(3)(B).....	16
Letters of Project Support.....	16
Official Resolution .....	16
Unique Entity Identifier and System for Award Management.....	16

## List of Figures

- Figure 1.1 – Cameron County Irrigation District No. 2 Location Map
- Figure 1.2 – Cameron County Irrigation District No. 2 Boundaries
- Figure 1.3 – Aerial View of “Canal F”
- Figure 1.4 – Cross Section Location Map for Canal “F”
- Figure 1.5 – Existing Cross Sections
- Figure 1.6 – Picture Showing Canal “F” at East Side (Facing Northeast)
- Figure 1.7 – Picture Showing Canal “F” Near Center of Canal Segment (Facing West)
- Figure 1.8 – Picture Showing Canal “F” Near Nelson Rd (Facing West)
- Figure 1.9 – Picture Showing Canal “F” Near Center of Canal Segment (Facing East)
- Figure 1.10 – Proposed Irrigation Pipe and Existing Cross Sections

## List of Tables

- Table 1 – Water Conservation Estimate
- Table 2 – Summary of Non-Federal Funding Sources
- Table 3 – Budget Proposal

## List of Appendices

- Appendix A – Contech Engineering Solutions A-2000 PVC
- Appendix B – “Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas”, Guy Fipps, and Craig Pope; “Report 316 Evaluation of Ground-Water Resources in the Lower Rio Grande Valley”, by the Texas Water Development Board, 1990
- Appendix C – USDA Soil Survey for Cameron County
- Appendix D – “Gulf Coast Jaguarundi Recovery Plan, First Revision,” U.S Fish and Wildlife Service; December, 2013; “Ocelot Recovery Plan, Draft First Revision”, U.S Fish and Wildlife Service Southern Region; August, 1990; USFWS List of Endangered Species in Texas
- Appendix E – “Economic Impact Estimate of Irrigation Water shortage on the Lower Rio Grande Valley Agriculture”, Texas A&M University AgriLife Extension, June, 2013
- Appendix F – CCID2 Water Conservation Plan and a Drought Contingency Plan
- Appendix G – Letters of Project Support
- Appendix H – CCID2 Grant Application Board Resolution
- Appendix I – CCID2 Accounting Balance Sheet

# Technical Proposal

## Executive Summary

Date: March 19, 2019

Applicant: Cameron County Irrigation District No. 2

26041 FM 510

San Benito, Texas 78586

Project Title: Conversion of Lateral 8 from Open Canal to a Pipeline




The Cameron County Irrigation District No. 2 (CCID2) is proposing to partner with the Bureau of Reclamation (Reclamation) for a Funding Group I Project to conserve water and energy. The proposed project consists of converting approximately 3,310 liner feet (lf) of the unlined open canal in a segment of Lateral 8 to underground pipeline. These improvements are expected to improve water deliveries by conserving approximately 338 acre feet per year of water. The conserved water is less water that will need to be pumped from the Rio Grande thus improving the reliability of the water supply for all users in the region. The resulting water conservation will reduce required pumping time needed to achieve the same water volume delivery thus increasing energy efficiency of the water delivery system by an estimated 13,600 kilowatt hours per year. The project is consistent with the established priorities of the Department of the Interior in that it utilizes science and best practices for managing land and water resources, modernizes existing infrastructure and greatly reduces maintenance demands. All of the proposed improvements are to be constructed on CCID2 property (none of the improvements will be located on a Federal Facility) and this project will be completed within 24 months. The construction phase of this project is estimated at 6 months, not considering schedule adjustments to accommodate necessary irrigation demands. The project can begin immediately upon execution of any grant agreement.

## Background Data

Cameron County Irrigation District No. 2 (CCID2) is located in the Lower Rio Grande Valley Region with its main office located in San Benito, Texas (See Figure 1.1). CCID2 boundary encompasses 64,459 acres and currently serves 55,151 acres of irrigated farmland where farmers grow citrus, vegetables, sugar cane, sorghum, corn and hay (See Figure 1.2).

CCID2 receives its water from the District's San Benito River Pump Station located in Los Indios, Texas on the eastern side of the Rio Grande. Pumped water from the Rio Grande is transported via two main earthen canals that deliver the entire district's agricultural and domestic demand. The district's distribution system consists of 241 miles of canals and pipelines including: 120 miles of unlined canals, 17 miles of lined canals,





# CAMERON COUNTY IRRIGATION DISTRICT No.2

CAMERON COUNTY IRRIGATION DISTRICT NO.2  
WATERSMART GRANT APPLICATION FY2019  
LOCATION MAP  
FIGURE I.I



**AMBIOTEC**  
CIVIL ENGINEERING GROUP, INC.  
5420 Paradise Lane Road  
Brownsville, Texas 78526  
Fax: (956)548-9399  
(956)548-9333

TYPE FIRM No. F-4126  
TXPLS REG No. 10095300

104 miles of pipeline, and 15 miles of resaca (oxbow lake). Of the 241 miles of canals, 137 miles are considered to be main canals and 104 miles are classified as lateral canals. In addition to the above list of open canals and pipelines, CCID2 has a storage reservoir with a capacity of 7,925 acre feet near the San Benito River Pump Station. Due to the large lengths of inefficient open unlined canals, CCID2's overall distribution conveyance efficiency is an estimated 60 percent.

All water right holders along the Rio Grande below Amistad Dam are part of the Lower Rio Grande Valley Watermaster System. The system is currently over allocated and during the past few decades the semi-arid watershed has experienced several long term droughts. In addition, the supply is further compromised by 1944 US-Mexico Treaty which allows Mexico to detain upstream flows and defer water deliveries up to five years in the amount 350,000 acre feet per year. The result is a system vulnerable to extreme drought and other inconsistent weather patterns.

The Lower Rio Grande Valley Watermaster System provides water to irrigation water right holders after municipal and industrial water right holders have been accounted for. The US share of storage in the Amistad-Falcon System is currently at 67.5% of its 3,015,842 acre feet conservation capacity. This is elevated from the 61.4% of normal conservation capacity a year ago at this time. However, inconsistent weather patterns can't be relied upon as a constant water source plus the area's population continues to grow, so water conservation improvements are crucial to long term water resource management. In fact, as recent as early February 2013, the capacity of Falcon Reservoir was only 32.9% of its capacity while Amistad Reservoir was at 45.3% capacity.

Currently, CCID2's irrigation water right is a total of 147,824 acre feet per year. In addition to their irrigation water rights, the CCID2 holds municipal/domestic water rights of 5,518 acre feet per year, municipal water rights of 6,390 acre feet per year, and industrial water rights 192 acre feet per year. The average annual water diverted by the CCID2 from 2011 through 2018 for all users was roughly 95,700 acre feet per year. The CCID2's primary municipal customers include the East Rio Hondo Water Supply Corporation (6,685 acre feet per year), City of San Benito (5,500 acre feet per year) and the City of Rio Hondo (890 acre feet per year). The CCID2 is the sole source of water for these municipalities, which together include a total population of nearly 50,000 residents.

The CCID2 obtains its water from the Rio Grande at the CCID2 San Benito River Pump Station. This pump station, constructed in 2005, includes eight pumps (2 – 150Hp, 50 cfs pumps and 6 – 300Hp, 100cfs pumps) and is powered by both electricity and natural gas.

The CCID2 has completed several projects with Bureau of Reclamation in the past, including:

1. Pumping Plant Rehabilitation (03-FC-60-1799)
2. Canal Rehabilitation (04-FC-60-1871)



3. Water 2025 Challenge Grant- Gate Replacement (05-FC-60-2017)
4. Water 2025 Challenge Grant- Canal Piping (07FC602235)
5. Water 2025 Challenge Grant- Canal Flow Measurement & Control Improvements (08-FC-60-2330)
6. 2016 WaterSMART Grant - Lateral “J” Open Channel to Pipeline (R16-FOA-DO-004)
7. 2017 WaterSMART Grant – Lateral “JN-1” Open Channel to Pipeline (R17AP00141)
8. 2017 WaterSMART Grant – Lateral “8” Open Channel to Pipeline – Under Construction (R17AP00138)
9. 2017 WaterSMART Grant – Lateral-“F” Open Channel to Pipeline – Under Design (R17AP00140)
10. 2017 WaterSMART Grant – Canal “E” Open Channel to Pipeline – Under Design (R17AP00139)
11. CCID2 is also a member of the Rio Grande Regional Water Authority that participated in the “Lower Rio Grande Basin Study”, prepared by the Bureau of Reclamation in 2013.
12. 2018 WaterSMART Grant – Lateral “F” Open Channel to Pipeline – Under Design (R18AP00156)
13. 2018 WaterSMART Grant – Lateral “C” Open Channel to Pipeline – Under Design (R18AP00157)
14. 2018 WaterSMART Grant – Automated Gates (Laterals J, 8, C, 15, & LI-1) – Under Design (R18AP00155)

Through CCID2’s financial partnership with the Bureau of Reclamation, the above projects are conserving roughly 45,460 acre feet of water per year (upon completion of all projects).


## **Project Location**

The Lateral 8 project is located in Cameron County, Texas approximately 2.5 miles S of San Benito, TX and approximately 6.2 miles NW of Rancho Viejo, TX (Figure 1.2). The approximate latitude of the project center is 26°5’9.07” N and longitude is 97°38’49.19”W.

## **Project Description**

The project consists of water savings, water supply reliability, and other components that meet the goals of the 2019 WaterSMART Funding Opportunity Announcement No. BOR-DO-19-F004. The proposed project includes converting approximately 3,310 lf of the open unlined canal to underground 36-inch PVC pipe. The location of Lateral 8 irrigation canal is shown in Figure 1.3. The conversion of Lateral 8 will conserve an estimated 338 acre-feet of water per year plus conserve 13,600 kilowatt hours per year of energy. The current unlined canal experiences water losses from seepage into the ground, evaporation from the surface, plant transpiration from canal bank and floating vegetation, and canal bank






15-0001 - 0008 - Preparation of a 2008 Reauthorized Water Application - FID# 0804 (04/15/08) - District Boundary and Project Components map

**CAMERON COUNTY IRRIGATION DISTRICT NO. 2  
 WATERSMART GRANT APPLICATION FY2019  
 DISTRICT BOUNDARY AND PROJECT COMPONENTS  
 FIGURE I.2**

**AMBIOTEC**  
 CIVIL ENGINEERING GROUP, INC.  
 5420 Paredes Line Road  
 Brownsville, Texas 78526  
 Fax (956)548-9399  
 (956)548-9333  
 TYPE FIRM No. F-4126  
 TPELS REG. No. 10005300





3,310 LF TO BE CONVERTED FROM  
OPEN CANAL TO PIPELINE

GAMBLE RD

LATERAL "8"

LATERAL "F"

JOINES RD

NARCISCO MARTINEZ HWY

LATERAL "LOS INDIOS"

732 RD

CAMERON COUNTY IRRIGATION DISTRICT NO. 2  
PROPOSED CONVERSION OF LATERAL "8"  
FROM CANAL TO PIPELINE  
FIGURE 1.3



**AMBIOTEC**  
CIVIL ENGINEERING GROUP, INC.

5420 Paredes Line Road  
Brownsville, Texas 78526  
Fax (956)548-9399  
(956)548-9333

TBPE FIRM No. F-4126  
TBPLS REG No. 10005300

8.1.3.331 - 0002 - Preparation of 4.800 WaterMain & Sewer Appointments - F1703.Dwg (C:\3331 - Utility Map-revised.dwg) 08/13/07



failures. Figures 1.4 and 1.5 shows the existing cross sections of the Lateral 8 and Figures 1.6 through 1.9 show pictures of the existing conditions of the irrigation canal. Replacing this open unlined canal with a pipe will require clearing and grubbing of the vegetation and canal debris, installing approximately 3,310 linear feet of PVC piping and associated tees and valves, and replacing several individual service laterals. The proposed piping will connect to the existing ditch on the west side of Gamble Rd. Downstream from the project, the proposed pipe will tie into an existing pipeline.

## **E.1 Evaluation Criteria**

### **E.1.1 Evaluation Criterion A - Quantifiable Water Savings**

The current unlined canal experiences water losses from seepage, evaporation, canal bank failures, and plant transpiration of which the significant quantifiable losses are caused by seepage, evaporation, and canal bank failures. By replacing the open unlined canal with PVC pipe (See Appendix A for products brochures), this project will nearly eliminate all of the water losses in this portion of Lateral 8.

From Texas A&M Department of Agricultural Engineering's, "Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas",<sup>1</sup> (See Appendix B); seepage rate calculations are based on typical canal soils as shown in the USDA Soil Survey for Cameron County (See Appendix C). Soils along this canal consist of Laredo Silty Clay Loam with a seepage rate of approximately 2.00 gallons per square foot per day. Evaporation rates were estimated utilizing the Texas Water Development Board's, "Report 316 Evaluation of Ground-Water Resources in the Lower Rio Grande Valley",<sup>2</sup> (See Appendix B). Lastly, the District has documented bank failures for this canal occurring on average three times per year. For the purpose of this application, it is assumed that the entire canal volume is lost when a bank failure occurs.


Using the above information and reference guidelines, the conserved water volume was calculated at approximately 338 acre feet per year or an annual transit loss reduction of 539 acre-feet per mile. The water conservation calculation is shown in Table 1 below.

---

<sup>1</sup> "Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas", Guy Fipps, and Craig Pope

<sup>2</sup> "Report 316 Evaluation of Ground-Water Resources in the Lower Rio Grande Valley", Wesley McCoy, Geologist, Texas Water Development Board, 1990





3,310 LF TO BE CONVERTED FROM OPEN CANAL TO PIPELINE

GAMBLE RD

LATERAL "8"

LATERAL "F"

JOINES RD

NARCISCO MARTINEZ HWY

LATERAL "LOS INDIOS"

732 RD

CAMERON COUNTY IRRIGATION DISTRICT NO. 2  
 PROPOSED CONVERSION OF LATERAL "8"  
 FROM CANAL TO PIPELINE  
 FIGURE 1.4



**AMBIOTEC**  
 CIVIL ENGINEERING GROUP, INC.


5420 Paredes Line Road  
 Brownsville, Texas 78526

Fax (956)548-9399  
 (956)548-9333

TBPE FIRM No. F-4126  
 TBPLS REG No. 10005300

6.3332 - 0002 - Preparation of 4.800 Waterfowl Hunt Appropriation - 7/10/04 by CAG/3/3/04 - Vicinity Map showing areas not to be





SECTION A-A  
SCALE=1"=50'



SECTION B-B  
SCALE=1"=50'

CAMERON COUNTY  
IRRIGATION DISTRICT NO. 2  
EXISTING LATERAL "8" CROSS SECTIONS



**AMBIOTEC**  
CIVIL ENGINEERING GROUP, INC.  
5420 Paredes Line Road  
Brownsville, Texas 78526  
Fax (956)548-9399  
(956)548-9333

TBPE FIRM No. F-4126  
TBPLS REG No. 10005300



CAMERON COUNTY IRRIGATION DISTRICT No.2



Figure I.6



Figure I.7



Figure I.8



Figure I.9

CAMERON COUNTY IRRIGATION DISTRICT NO.2  
EXISTING CONDITIONS



AMBIOTEC  
CIVIL ENGINEERING GROUP, INC.

5420 Paredes Line Road    Fax (956)548-9399  
Brownsville, Texas 78526    (956)548-9333

TBPE FIRM No. F-4126  
TBPLS REG No. 10005300

<b>Table 1</b>		
<b>Water Conservation Estimate</b>		
Lateral 8 Surface Area	2.51	Acres
Lateral 8 Cross Sectional Area	184.00	Feet
Lateral 8 Canal Volume	13.98	Acre Feet
Wetted Perimeter	38.20	Feet
Average Depth	6.50	Feet
Seepage Rate (weighted average for Benito Clay, Harlingen Clay, and Olmito Silty Clay)	2.00	Gallons per Square Foot per of Wetted Perimeter per Day
<b>Estimated Seepage</b>	<b>283.27</b>	Acre Feet per Year
Evaporation Rate for Cameron County	61	Inches per Year
<b>Estimated Evaporation</b>	<b>12.75</b>	Acre Feet per Year
Failures per Year	3	
Full Irrigation Canal Volume	13.98	Acre Feet
<b>Estimated Bank Failure Losses</b>	<b>41.94</b>	Acre Feet per Year
<b>TOTAL WATER CONSERVATION ESTIMATED</b>	<b>337.96</b>	Acre Feet per Year


By replacing the unlined canal with 36-inch diameter PVC pipe, the proposed piping system will decrease the measureable losses to less than 1-percent of the calculated water losses shown in Table 1. Also, the pipe system will require less push-water (hydraulic pressure head) to counteract the resistance from the canal debris and vegetative growth along the existing banks.

Water is currently diverted into the Lateral 8 distribution system from Canal R.H.L, one of the main canals in CCID2's system. Downstream of the proposed project, the pipeline will tie into an existing pipeline. Lateral 8 proposed improvements will better manage the water delivered to the over 243 acres immediately served by the existing unlined open canal segment of Lateral 8. Figure 1.10 shows the existing unlined canal cross section with the proposed irrigation pipe cross section.


The unlined portion of Lateral 8 distribution system provides water to over 243 acres and the total estimated average annual demand for this system lateral over the last two years was approximately 944 acre feet. Adding the estimated 338 acre feet lost to seepage, evaporation, and bank failure for this canal segment results in 1,282 acre feet of water being more efficiently managed as a result of the project.

The CCID2 has pumped an average of 95,700 acre feet annually in recent years. Since majority of the district's distribution system relies on unlined and open earthen canals for delivery, the water losses in the distribution system are estimated at nearly 40 percent, or final delivery of only 57,420 acre feet per year. When comparing the water savings for the





SECTION A-A  
SCALE=1"=50'



SECTION B-B  
SCALE=1"=50'

CAMERON COUNTY  
IRRIGATION DISTRICT NO. 2  
PROPOSED LATERAL "8" CROSS SECTIONS



**AMBIOTEC**  
CIVIL ENGINEERING GROUP, INC.  
5420 Paredes Line Road  
Brownsville, Texas 78526  
Fax (956)548-9399  
(956)548-9333

TBPE FIRM No. F-4126  
TBPLS REG No. 10005300

proposed improvements for Lateral 8, 338 acre feet, the annual water savings expressed as a percentage of the district's supply is 0.35%. When considering the 1,282 acre feet of water delivered through Lateral 8, the annual water savings percentage is 26.4%.

Upon completion of the proposed improvements, CCID2 will verify the water loss calculations by installing temporary flow metering devices at Lateral 8 influent canal gate structure and at individual customer's outlet structures. Water seepage and evaporation losses will be determine by subtracting the influent measurements with the delivered water and pipe volumes. CCID2 will prepare a final report, for submittal to the Bureau of Reclamation, on the findings of the water conservation measures resulting from the proposed improvements included in this project.

### **E.1.2 Evaluation Criterion B: Water Supply Reliability**

The proposed project improves the reliability of the water supply for our local providers and users. The Lower Rio Grande Valley has been subject to periods of drought on several occasions over the last decade. Additionally, inefficiencies resulting from aged infrastructure combined with high rates of water loss from evaporation, infiltration and bank failures threaten the reliability of the water supply for all users in the region many of which live in rural and economically disadvantaged areas (32% of population is at or below the poverty line). As indicated in Section E.1.1, the proposed project along Lateral 8 would eliminate a loss of over 338 ac-ft of water per year. This is 338 ac-ft less of water that will need to be pumped from the Rio Grande that will instead be available for other users. This is one of many open canals that are utilized by local irrigation districts to deliver water to users and the combined impact of all the water lost through evaporation, infiltration and bank failures, in addition to the water being used by vegetation that grows along the canals, has a significant impact on the quantity of water available to South Texas users. The importance of water conservation through the conversion of canals to underground pipelines has been documented by several groups including the Region M Planning Group in association with the Texas Water Development Board. Implementation of this project in concert with other similar open canals in the region could substantially increase the water available for the entire Lower Rio Grande Valley.

The project has strong support in the region including from the East Rio Hondo Water Supply Corporation (ERHWSC). A letter of support from ERHWSC is included in Appendix G. The project helps set an example for other water supply agencies in the region on how both water and money can be saved through the implementation of infrastructure upgrades such as described in this project. Additionally it provides incentive for local farmers to implement additional water conservation measures through the EQUIP



program since any farmer applying for funding off of the proposed project can enter into an agreement with the District to install their pipelines at no additional cost to them. .

The project will also provide a benefit to threatened and endangered species in the Lower Rio Grande Valley. Specifically, much of the rural portion of Cameron County is prime habitat for both the Ocelot and Jaguarundi and the Department of the Interior has several wildlife areas throughout the County, including a large USFWS tract of land approximately 2 miles E of the project site. Additionally, the Las Palomas – Tucker – Deshazo Unit Wildlife Management Area is located approximately 2.6 miles west of the site. The site is also located directly next to a resaca with a vegetated buffer along its banks. Irrigation water is pumped from the Rio Grande, into the natural Resaca networks that traverse the County. These resacas are used by native wildlife, including the Ocelot and Jaguarundi, as a fresh water source for drinking and maintaining riparian habitat, so reducing water losses in the region improves the reliability of water supply not only for residents, but also for critically threatened and endangered wildlife species. Additionally, putting this irrigation canal underground removes a barrier for wildlife to access the freshwater resaca source and vegetated area that could serve as habitat. None of the vegetated area along the resaca bank will be disturbed as a result of this project. All clearing and construction will occur strictly within the right-of-way of the existing irrigation canal.

### **E.1.3. Evaluation Criterion C: Implementing Hydropower**

The proposed project does not include the implementation of hydropower.

### **E.1.4. Evaluation Criterion E: Complementing On-Farm Irrigation Improvements**

The segment of Lateral 8 distribution system included in this project provides water to over 243 acres of which farmers grow vegetables, sugar cane, sorghum, corn and hay. On-Farm Improvements are controlled by the individual land owners. However, the placement of Lateral 8 into a pipeline will increase the water volume and pressure to allow landowners to install more efficient localized irrigation, drip irrigation, pumped sprinkler system or lay flat irrigation poly pipe. Additionally, any farmer applying for EQUIP funding off of our proposed projects can enter into an agreement with CCID2 to install their pipelines at no additional cost to them. Under the agreement, CCID2 contributes the labor and equipment required to install the funded pipeline.

### **E.1.5. Evaluation Criterion D: Department of the Interior Priorities**

The conversion of Lateral 8 from open unlined canal to a pipeline utilizes science and best practices for managing land and water resources. Projects such as this one that involve eliminating open irrigation canals in lieu of underground pipelines to conserve water have been identified by such groups as the Region M Planning Group in association of the Texas Water Development Board. The conversion will eliminate virtually all losses occurring from seepage, evaporation and bank failures. Such losses are currently estimated at approximately 338 ac-ft annually over the length of the proposed project. Drought conditions have become more prevalent over the last decade and projects like this one that result in reduced water demand are essential to ensuring adequate water supplies for future use.

Water for this Canal is currently diverted from the “Entry Canal” that connects directly to the Rio Grande. The Rio Grande provides the majority of the freshwater drinking supply to several downstream communities in addition to being used to maintain water in the resaca networks that traverse southern Cameron County. Water supply in the areas resacas are critical to sustaining habitat and wildlife within the designated area and any measure to reduce the water volume diverted from the Rio Grande is consistent with Department of Interior priorities.

The project also involves modernization of existing infrastructure, another one of the priorities listed by the Department of the Interior. The project will construct new underground pipeline in lieu of an open channel that effectively reduces water losses, conserves water and reduces maintenance requirements since there will no longer be vegetation and overgrowth that needs to be maintained along the canal.

### **E.1.6. Evaluation Criterion F: Implementation and Results**

#### **Subcriterion No. F.1 – Project Planning**

The Conversion of Lateral 8 from open unlined canal to a pipeline project has been identified and prioritized in past District planning efforts. The CCID2 has adopted a Water Conservation Plan and a Drought Contingency Plan (included in Appendix G) to ensure that water is used efficiently within the operations of the district during normal operations and during drought conditions. These plans are developed to address several strategies to decrease the overall water consumption, reducing system water conveyance losses, and improving efficiency of water use. CCID2’s staff and operators have first-hand knowledge of the delivery inefficiencies and the structural conditions of the conveyance system.



CCID2 identifies this type of project and ranks them based on the most cost effectiveness in regards to water and energy conservation to the district.

**Subcriterion No. F.2 – Performance Measures**

Upon completion of the proposed improvements, CCID2 will install temporary flow metering devices at the Lateral 8 influent flume gate structure and at individual customer's outlet structures. Water losses will be determined by subtracting the influent measurements with the delivered water and pipe volumes. CCID2 will prepare a final report, for submittal to the Bureau of Reclamation, on the findings of the water conservation measures resulting from the proposed improvements included in this project.

**Subcriterion No. F.3 – Readiness to Proceed**

CCID2 is ready to begin the project immediately, if awarded, upon receiving notification to proceed. Preliminary engineering work has already begun and survey crews have collected cross-sectional topographic data to assist with preliminary design considerations, including pipe sizing and pipe placement within the existing canal right-of-ways in addition to the development of project costs. Overall, it is estimated that engineering design including material procurement would be completed within a six-month time frame and construction phase would be completed within another six-months. Post project reporting on the performance of the proposed improvements would then continue over the following twelve months. A detailed breakdown of the project schedule may be viewed in the chart on the following page.

There are no anticipated permits that will be required prior to construction of the project. The project does not include the crossing of any TxDOT or Cameron County right-of-ways thus will not require any utility crossing permits. The Board of Directors is in complete support of the proposed project as evidenced by the Official Resolution included in Appendix I and is ready to dedicate the 55% project matching funds indicated in the project budget. There are no new policies or administrative actions that will be required to implement this project beyond the typical board approvals for the selection of material suppliers as part of the competitive bidding process. As indicated in the list of previous BOR projects on pages 2-3, CCID2 has completed several previous projects vary similar in scope to the project proposed herein. As such, the District has a clear idea of all likely environmental requirements and potential permitting issues. Since the entire project and all earthwork will take place within an existing District right-of-way that has already been disturbed, the only anticipated clearance that is anticipated is with the State Historic Preservation Office (SHPO). All previous projects have been coordinated through the SHPO and there are no anticipated hurdles expected in implementing this project. The cost estimate for environmental compliance that has been included in the project budget is based off compliance costs incurred during previous projects of nearly identical scope.

TASKS	Proposed Schedule (24 Months)																							
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Design Phase (6 Months):																								
Notice to Proceed																								
Collect Field Surveying Data																								
Finalize Design																								
Material Procurement																								
Construction Phase (6 Months):																								
Site Clearing and Demolition																								
Pipeline Installation																								
Tie-Ins and Misc. Improvements																								
Final Clean Up and Start Up																								
Project Management and Reporting (12 Months):																								
Post Project Reporting and Performance																								
Final Report																								

**E.1.7 Evaluation Criterion H: Nexus to Reclamation Project Activities**

The Bureau of Reclamation has funded numerous projects in the Lower Rio Grande Valley for several irrigation and municipal entities. All the projects directly and indirectly affect water conservation for the entire basin which transfers to benefits to all users in the Lower Rio Grande Valley Watermaster System. CCID2 experience with previously funded Bureau of Reclamation projects are listed in Background Data Section of this report.

The Lower Rio Grande Basin Study was completed by the Bureau of Reclamation in December, 2013. The report was completed in partnership with the Rio Grande Regional Water Authority, including its 53 entity committee, the TCEQ Region M Planning Group, the Texas Commission on Environmental Quality, the Texas Water Development Board,



and the International Boundary and Water Commission. The study evaluated future water demands, future water supply, weather inconsistencies and other factors impacting the supply and demand for water in the Lower Rio Grande Basin. The Rio Grande Regional Water Authority is made up of eight counties including Hidalgo, Willacy and Cameron Counties. CCID2 is an active member of the Rio Grande Regional Water Authority.

**E.1.8. Evaluation Criterion G: Additional Non-Federal Funding**

CCID2 is seeking federal grant funds of \$175,842 and the remaining funds for the project will be provided by CCID2. With a total project cost of \$390,760 the Non-Federal funding percentage is 55.0 percent.

**Project Budget**

**Funding Plan and Letters of Commitment**

CCID2 will fund the entire non-grant portion of this project, \$217,768 or 55-percent of the project costs. No 3<sup>rd</sup> Party funds will be used on this project. CCID2 portion of the funds include \$35,026 of in-kind contributions including labor and equipment costs. CCID2 cost associated with material and contractual costs will be compensated through the District’s account reserve funds. Labor and equipment in-kind services will be paid for from the District’s general operating budget. The District’s accounting balance sheet (included in the Appendix J) shows that sufficient funds are available for the completion of this project. Table 2 below shows the Summary of Non-Federal Funding Sources.

<b>Table 2</b>	
<b>Summary of Non-Federal Funding Sources</b>	
<b>Funding Sources</b>	<b>Funding Amounts</b>
Non-Federal Entities	
Cameron County Irrigation District No. 2	\$214,918
<b>Non-Federal Subtotal:</b>	<b>\$214,918</b>
Other Federal Entities	
None	\$0
<b>Other Federal Subtotal:</b>	<b>\$0</b>
Requested Reclamation Funding:	<b>\$175,842</b>
<b>TOTAL PROJECT FUNDING:</b>	<b>\$390,760</b>

## **Budget Proposal**

Table 3 shows the Project Budget Proposal.

## **Budget Narrative**

### **Salaries and Wages**

The District personnel involved in this project along with their salaries and fringe costs are detailed in Table 3. The General Manager, Mrs. Sonia Lambert, has been District Manager for forty years. CCID2 has completed several Bureau of Reclamation improvement projects under the management of Mrs. Lambert. The Field Supervisor for the proposed work will be Mr. Jesse Moncivaiz. Mr. Moncivaiz has 16 years of experience as a field supervisor and has been with CCID2 for 24 years.

The District also plans to utilize two construction crews made up of 3 men. Both crews are able to complete the work needed for this project. The fringe benefits of 14.48%, as shown in Table 3, include Social Security, Retirement, Health Insurance, Paid Leave, Medicare, Unemployment and Workers Compensation.

The project budget assumes two crews for eight, 40 hour work-weeks to construct the proposed improvements. The pipeline is roughly 3,310 feet long, the combined efforts of both work crews can lay roughly 600 feet per week, resulting in approximately six weeks of pipe installation. The other pipeline appurtenances will be installed as they are encountered and will take roughly a week to construct.

The construction time for two crews is budgeted at just over six, 40 hour work-weeks or 250 hours and the Field Supervisor time is estimated at 15 hours per week during construction and an additional 40 hours for the managing of in-kind services provided by the district. The General Manager's (Sonia Lambert) time is budgeted at 80 hours for the length of the project to manage all phases of the project.

### **Fringe Benefits**

The fringe benefits of 14.48%, as shown in Table 3, include Social Security, Retirement, Health Insurance, Paid Leave, Medicare, Unemployment and Workers Compensation.

### **Travel**

There is no travel anticipated on this project.



**Table 3  
BUDGET PROPOSAL**

	<b>Unit Cost</b>	<b>QTY</b>	<b>Unit</b>	<b>Unit Extension</b>	<b>CCID 2</b>	<b>USBR</b>	<b>Total Cost</b>
<b>DISTRICT EXPENSES</b>							
<b>Salaries and Wages</b>							
General Manager	\$68.70	80	HR	\$5,496	\$3,023	\$2,473	\$5,496
Field Staff Supervisor	\$29.30	130	HR	\$3,809	\$2,095	\$1,714	\$3,809
Crew #1	\$40.92	300	HR	\$12,276	\$6,752	\$5,524	\$12,276
Crew #2	\$38.69	300	HR	\$11,607	\$6,384	\$5,223	\$11,607
<b>Fringe Benefits (14.48%)</b>							
General Manager	\$9.95	80	HR	\$796	\$438	\$358	\$796
Field Staff Supervisor	\$4.24	130	HR	\$551	\$303	\$248	\$551
Crew #1	\$5.93	250	HR	\$1,483	\$815	\$667	\$1,483
Crew #2	\$5.60	250	HR	\$1,400	\$770	\$630	\$1,400
<b>Equipment</b>							
D6 Dozer	\$46.89	100	HR	\$4,689	\$2,579	\$2,110	\$4,689
Excavator (JD 290)	\$84.91	250	HR	\$21,228	\$11,675	\$9,552	\$21,228
<b>Supplies/Materials</b>							
stakes and spray paint	\$350.00	1	LS	\$350	\$193	\$158	\$350
<b>SUBTOTAL</b>					<b>\$35,026</b>	<b>\$28,658</b>	<b>\$63,685</b>
<b>PROJECT EXPENSES</b>							
<b>Supplies/Materials</b>							
36" PVC Pipe	\$70.00	3310	LF	\$231,700	\$127,435	\$104,265	\$231,700
15" PVC Pipe	\$10.00	150	LF	\$1,500	\$825	\$675	\$1,500
54" Reinforced Concrete Pipe	\$120.00	72	LF	\$8,640	\$4,752	\$3,888	\$8,640
36"x15" Tee	\$1,500.00	5	EA	\$7,500	\$4,125	\$3,375	\$7,500
36" Elbows	\$1,700.00	6	EA	\$10,200	\$5,610	\$4,590	\$10,200
15" Elbows	\$225.00	5	EA	\$1,125	\$619	\$506	\$1,125
36" Fresno Gate	\$2,000.00	1	EA	\$2,000	\$1,100	\$900	\$2,000
15" In Line Gates	\$1,200.00	5	EA	\$6,000	\$3,300	\$2,700	\$6,000
14" X 15" Alfalfa Valves	\$300.00	5	EA	\$1,500	\$825	\$675	\$1,500
15" Draw Bands	\$10.00	20	EA	\$200	\$110	\$90	\$200
Concrete	\$105.00	10	CY	\$1,050	\$578	\$473	\$1,050
<b>Engineering Contractual</b>							
Registered Professional Engr.	\$200.00	32	HR	\$6,400	\$3,520	\$2,880	\$6,400
Sr. CAD Technician	\$105.00	60	HR	\$6,300	\$3,465	\$2,835	\$6,300
CAD Technician	\$85.00	80	HR	\$6,800	\$3,740	\$3,060	\$6,800
Administration Assistant	\$65.00	24	HR	\$1,560	\$858	\$702	\$1,560
Registered Professional Surv.	\$135.00	60	HR	\$8,100	\$4,455	\$3,645	\$8,100
Survey Crew	\$175.00	100	HR	\$17,500	\$9,625	\$7,875	\$17,500
<b>Other Contractual</b>							
Environmental Compliance		1	LS	\$2,500	\$1,375	\$1,125	\$2,500
Geotechnical Testing		1	LS	\$3,500	\$1,925	\$1,575	\$3,500
<b>Other</b>							
Reporting	\$3,000.00	1	LS	\$3,000	\$1,650	\$1,350	\$3,000
<b>SUBTOTAL</b>					<b>\$179,891</b>	<b>\$147,184</b>	<b>\$327,075</b>
<b>Total Direct Cost</b>					<b>\$214,918</b>	<b>\$175,842</b>	<b>\$390,760</b>
<b>Total Indirect Cost</b>					<b>\$0</b>	<b>\$0</b>	<b>\$0</b>
<b>TOTAL PROJECT COSTS</b>					<b>\$214,918</b>	<b>\$175,842</b>	<b>\$390,760</b>

## **Equipment**

CCID2 plans on using two pieces of equipment included in Table 3, a D6 Bulldozer and JD 290 Excavator, already owned and maintained by the district. Equipment rates are based on the "Construction Equipment Ownership and Operating Expenses Schedule, Region VI" by the US Army Corps of Engineers, November 2011.

The JD 290 excavator is estimated to be operating about 80% - 90% of the 320 hours budgeted and be on standby the other 10 - 20% of the time. For the 160 hours budgeted for the D6 Bulldozer, it is estimated to be operating 90% of the time and be on standby 10% of the time.

## **Materials and Supplies**

The 36-inch and 15-inch PVC pipe unit pricing are based on recent price quotes from Aguaworks, Contech, and other suppliers averaging roughly \$70/LF and \$10/LF respectively. The unit prices for the PVC tees and elbows were provided by Soileau Industries. The unit prices for the gates, alfalfa valves and draw bands were provided by Fresno Valve and Casting, Inc. The unit prices of \$120/LF for 54-inch reinforced concrete pipe (RCP) and ready-mix concrete (\$105.00/cubic yard), to be used for the irrigation wells and gate valves, were provided by CAPA. Supplies and Materials line item are too numerous to quantify; however, the estimate of \$350 is based on previous project costs of similar size.

## **Contractual**

Professional Services - Ambiotec Civil Engineering Group, LLC (Ambiotec) will provide surveying and engineering services to construct the project. Services include surveying the canal right of way for boundary and field topography. Designing engineering construction plans and specifications, construction stake-out for the proposed pipeline and assistance throughout construction. The Engineer will also assist with the request for proposals for material quotations and for construction material testing services for required soil and concrete tests. A flat rate of \$3,500 has been estimated for construction material testing based on experience with previous projects at similar project sites. The total estimated cost for this contractual portion of the project is approximately \$46,660 for surveying and engineering services plus \$3,500 for construction material testing.

Material Supplies - CCID2 is a public entity operating under the Texas Water Code and subject to those procurement standards for construction proposals and materials over \$25,000. It is assumed that three sets of materials quotations will be required. For contracts over \$75,000, the public bidding process will be required which includes two



public advertisements in a general circulated newspaper. It is assumed that two public request for bidders will be required to provide bids.

### **Environmental and Regulatory Compliance Costs**

The District has included in its budget a flat rate of \$2,500, cost for Environmental and Regulatory Compliance. While the amount of work that may be necessary for environmental clearance is difficult to predict and will be determined by initial notification of the regulatory agencies, previous experience working at similar sites supports the estimated rate of \$2,500. Notification and required report costs are included in the \$2,500.

### **Other Expenses**

The anticipated project reporting costs are estimated at \$3,000 which includes testing of the pipeline and evaluation of metered flow to verify and document the water savings.

### **Indirect Costs**

There are no anticipated indirect costs on this project.

## **Environmental and Cultural Resources Compliance**

The proposed project will be constructed by CCID2 staff. Staff will be instructed to minimize impacts to local environmental sensitive areas and adjacent landowners. All proposed improvements are to be constructed within the CCID2 existing right-of-way (ROW) which has been previously disturbed. To protect against any environmental damages, CCID2 will coordinate with Federal, State and Local regulatory agencies to ensure all required environmental regulations are followed. Below are the responses to the ten (10) questions presented in Section H.1 of the Funding Opportunity Announcement No. BOR-DO-19-F004

1. Since the project will include soil excavation, the creation of dust is a strong possibility. CCID2 crews will sprinkle water to control dust creation during construction. All construction will occur within the existing canal right-of-way on land that has already been disturbed. The work will not disturb existing animal habitat and the end result will actually benefit threatened and endangered species in the area by removing physical barriers within existing habitat corridors and by conserving water to ensure future supply for animal species in the region.
2. While no threatened or endangered species have been observed in the project area, both the Ocelot and Jaguarundi are listed species that could be present in the area.

However, habitat will not be removed as a result of implementing this project and all construction will be located within the existing canal right-of-way. The canal is routinely maintained by CCID2 maintenance crews and doesn't provide sufficient habitat for endangered species. The area is not designated as a protected habitat by the US Fish and Wildlife Service. In any case, CCID2 will work with all Federal, State and Local regulatory agencies to ensure the project follows any required federal environmental regulations.

3. There are no wetlands or surface waters that fall under CWA jurisdiction within the project boundaries. The Corps of Engineers does not regulate irrigation canals and drainage ditches.
4. Portions of the CCID2 water conveyance system was constructed 1903.
5. The project proposes to connect to an existing influent control structure and service laterals to adjacent farm land. These features were constructed, modified and improved on an as-needed basis over the last 60 years.
6. CCID2 doesn't own any structures that may qualify for the National Register of Historic Places. The Environmental Compliance Report will coordinate with the Texas State Historical Preservation Office for approval prior to the commencement of the construction work.
7. There are no known archaeological sites in the project area. The Environmental Compliance Report will coordinate with the Texas State Historical Preservation Office and other applicable review agencies for approval prior to the commencement of the construction work.
8. This project will have indirect positive effect on low income or minority populations. The proposed project will conserve water and energy required to provide irrigation water to the area adjacent to Lateral "E". This results in a cost savings for the CCID2 and the public of which 32 percent is at or below the poverty rate
9. There are no tribal lands in the project area.
10. The project will not contribute to the continued existence or spread of noxious weeds or non-native species.

## **Required Permits and Approvals**

The Environmental Compliance Report will coordinate with and obtain approvals from multiple Federal and State environmental agencies prior to the beginning of the construction phase of this project. No permits are anticipated to be required, but any requested permit coming from the Environmental Compliance document will obtain approval prior to the beginning of construction. The project does not include the crossing of any TxDOT or Cameron County right-of-ways thus will not require any utility crossing permits.



## **Requirements for Agricultural Operations under P.L. 111-11, Section 9504(a)(3)(B)**

The applicant agrees to the following conditions if awarded funds for the proposed project:

- Not to use any associated water savings to increase the total irrigated acreage of the applicant
- Not to otherwise increase the consumptive use of water in the operation of the applicant, as determined pursuant to the law of the State of Texas

## **Letters of Project Support**

See Appendix H for the letter of support from East Rio Hondo Water Supply Corporation and Rio Grande Regional Water Authority.

## **Official Resolution**

CCID2 adopted a resolution for this Grant Application on March 14, 2019. A copy of the Resolution is included in Appendix H.

## **Unique Entity Identifier and System for Award Management**

CCID2 is registered in the System for Award Management (SAM) and its unique entity identifier is: 048459937 / 6J2J5

CCID2 will maintain an active SAM registration with current information at all times during which it has an active Federal award or application plan under consideration by a Federal awarding agency.

## List of Appendices

Appendix A – Contech Engineering Solutions A-2000 PVC

Appendix B – “Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas”, Guy Fipps, and Craig Pope; “Report 316 Evaluation of Ground-Water Resources in the Lower Rio Grande Valley”, by the Texas Water Development Board, 1990

Appendix C – USDA Soil Survey for Cameron County

Appendix D – “Gulf Coast Jaguarundi Recovery Plan, First Revision,” U.S Fish and Wildlife Service; December, 2013; “Ocelot Recovery Plan, Draft First Revision”, U.S Fish and Wildlife Service Sothern Region; August, 1990; USFWS List of Endangered Species in Texas

Appendix E – “Economic Impact Estimate of Irrigation Water shortage on the Lower Rio Grande Valley Agriculture”, Texas A&M University AgriLife Extension, June, 2013

Appendix F – CCID2 Water Conservation Plan and a Drought Contingency Plan

Appendix G – Letters of Project Support


Appendix H – CCID2 Grant Application Board Resolution

Appendix I – CCID2 Accounting Balance Sheet



**Appendix A**  
**Contech Engineering Solutions A-2000 PVC**

## A-2000™ PVC Pipe for Storm Sewers and Drainage





# Selecting Performance Storm Sewers and Drainage Systems


Drainage systems are required to meet multiple criteria. The choice of a particular material depends upon a number of factors; however, the best choice is the one that yields the best performance over the project life cycle.

## Thermoplastic Storm Sewer and Drainage Pipe

In recent years, the use of thermoplastic pipe for stormwater drainage systems has gained wide acceptance—based upon performance and economic advantages when contrasted with more conventional drainage pipe materials. **However, when it comes to performance, not all thermoplastic storm sewer pipes are equal.** There are distinct differences between A-2000 Polyvinyl Chloride (PVC) drainage pipe and other drainage pipes that can affect overall pipe system performance.

### Contech® A-2000 PVC Drainage Pipe: Available in Diameters 4”-36” and 14’ or 22’ lengths.

Originally developed in the early 1980’s, A-2000 has built an outstanding performance history that’s setting the standard for gravity flow, sanitary sewer applications. The material advantages offered by PVC—plus the innovative, double wall design with the unique, patented gasketed joint system—makes A-2000 the ideal choice for stormwater drainage systems. Now you can have all of the advantages without the limitations of HDPE or reinforced concrete pipe.



Compact A-2000 PVC profile is stable and not subject to local buckling like HDPE.



## Strength

A-2000’s PVC compound provides **6 times** greater long-term material stiffness as compared to HDPE drainage pipe materials. And A-2000 pipe, **UNLIKE** HDPE drainage pipe, has a minimum 46 pipe stiffness for **ALL** diameters.

## Minimum Specified Pipe Stiffness (73°)\*

Pipe Diameter	PVC ASTM F949	HDPE AASHTO M294
12	46	50
15	46	42
18	46	40
24	46	34
30	46	28
36	46	22

\*Actual A-2000 pipe stiffness values are 50 psi

## Better deflection control

When compared to other thermoplastic pipes on the market, A-2000 stands up to the test. In fact, it comes out on top.

When installed in accordance with ASTM D2321, A-2000 provides excellent shape control (performance).

The difference between effective pipe stiffness of A-2000 and HDPE drainage pipe during construction on a summer day can result in A-2000 being as much as **3 TIMES STIFFER**. This significant stiffness advantage, combined with PVC’s lower strain sensitivity and temperature sensitivity, means A-2000 can be installed with conventional flexible pipe practice and not experience excessive shape distortions.



**Heights of Cover**

Based on research done under the National Cooperative Highway Research Program, AASHTO has revised its plastic pipe design methods. AASHTO designs now include wall profile stability, soil arching and deflection as design considerations. Unstable wall profiles fail by local buckling rather than by ring compression or ring buckling. This research demonstrates that the A-2000 profile is stable while others, like those used for HDPE M294 pipe, are not.

A-2000 PVC pipe can be used with 1 foot of cover under highway loading. Current AASHTO LRFD Design Methodology has required all thermoplastic pipes to have a minimum height of cover of 2 feet under pavement. This requirement was derived from a Minnesota DOT Research Report (2005) that studied HDPE pipe performance under highway loading. The report indicates significant thermal expansion of HDPE pipe under shallow fills. PVC pipe was not incorporated in this study, and it should be noted that HDPE experiences four times more thermal expansion than PVC.

When selecting a system based on pipe stiffness, material strength and structural capability, A-2000 PVC far exceeds the performance characteristics of HDPE drainage pipe.



A comparison of cover heights using AASHTO design methodology and H2O live loading for A-2000 and a major manufacturer's M294 HDPE pipe are summarized below.

**A-2000 vs. M294 HDPE (AASHTO Heights of Cover)**

Pipe Type/Specification	Allowable Height of Cover	Allowable Structural Backfill	Min. Compaction	Min. Trench
PVC A-2000 - ASTM F949	2'-20'	A-1-a, A-1-b, A-3 A-2-4, A-2-5	90%	1.5 X O.D. + 12"
	21'-35'	A-1-a, A-1-b, A-3	95%	1.5 X O.D. + 12"
Corrugated HDPE - AASHTO M294	2'-10'	A1-a, A1-b, A-3	95%	O.D. + 36"
	11'-20'	A-1-a	95%	3.0 x O.D.
	21'-35'	Not Allowed		




## Durability, Service Life

PVC materials used in the manufacture of gravity flow pipe offer excellent resistance to conventional corrosion and abrasion. In fact, profile wall PVC pipe has been shown to have better abrasion resistance than reinforced concrete pipe in side-by-side laboratory testing at California State University.

PVC and HDPE do **not** provide equal long-term durability performance. Under loading or localized tensile stress, some grades of HDPE are subject to environmental stress cracking—also known as slow crack growth. Exhibited as premature rupture, this phenomenon can occur when stressed HDPE plastics are attacked by a reagent (even storm runoff) that causes cracking or rupture at stress levels well below design performance expectations.

PVC pipe is not threatened by this type of cracking. When you consider durability and service life, A-2000 PVC far exceeds the performance characteristics of HDPE drainage pipe. (See the National Cooperative Highway Research Program study conducted by Drexel University, March, 1999: "HDPE Pipe: Recommended Material Specifications and Design Requirements".)



Contech A-2000 PVC far exceeds the durability and service life of HDPE drainage pipe.



# Hydraulic Efficiency

## A-2000 vs. Concrete Pipe

Thermoplastic pipes, with smoother interiors and fewer joints, reduce resistance to flow and are hydraulically more efficient than conventional (i.e., RCP) storm drainage pipe materials. Flow testing conducted in 2002 by the Utah Water Research Laboratory concluded

A-2000 PVC Pipe, with its inner wall formed over a polished mandrel, has the lowest wall friction factor (Manning's "n" = .009) of any thermoplastic pipe available and offers real advantages compared to RCP (n = .012- .013). This added efficiency means A-2000 can be designed as a smaller and less expensive pipe, with less excavation due to flatter pipe slopes and less manhole/junction box depth requirements.

## A-2000 vs. HDPE Pipe

Hydraulic tests performed at a major United States Water Research Laboratory led researchers to conclude that HDPE drainage pipe's "n" factor varied "depending upon the smoothness of the liners" and "the bonding of the liner to the corrugations made the pipe interior somewhat wavy." Once installed, HDPE pipe walls are subject to local buckling (NCHRP Report 438) and the measured waviness increases with load. Using the method derived to estimate the effective Manning's "n" factor, Manning's "n" values of 0.017-0.022 provide a more accurate representation of HDPE's hydraulic efficiency when in-service and under load.

A-2000 PVC pipe, with its engineered, stable profile, is designed to **NOT** buckle.

**When you're selecting a system based on hydraulic efficiency, A-2000 PVC pipe far exceeds the performance limitations of HDPE and RCP drainage pipe.**



A-2000 PVC has a smooth, glossy interior for uninterrupted flow.





### The Need for Tight Joints

Storm sewers have always presented special needs for tight jointing systems. Because of their function, they are subject to rapidly changing flow levels. The sudden rise and fall of flow levels leaves storm sewers susceptible to backfill migration into the sewer unless tight joints are used. This loss of backfill reduces the soil support of the pipe and causes settlement at the surface. Where storm sewers are below the existing water table, water tight joints are needed to prevent infiltration and maintain storm sewer capacity.

A-2000's long, 22-foot lengths and soil/water tight joints clearly make it the preferred choice with regard to system tightness. In comparison, RCP has many joints—increasing the opportunity for soil infiltration and settlement. And with A-2000 you don't have to specify special jointing requirements. Watertight gasketed joints are standard with A-2000.

### Handling and Installation



A-2000's easy handling weight and the availability of up to 22-foot lay lengths often result in reduced labor costs and more economical installation. Compared to heavy-weight and short-length RCP, A-2000 can be installed with greater ease and lower cost. And contrasted to HDPE, A-2000 has added beam strength—which means better line and grade control, increasing crew efficiency. Plus, A-2000 requires less trench width, lowering excavation costs and speeding installation.

### The Performance Choice

With the increasing demands on our drainage and storm sewer systems, products designed and proven to provide the best performance over the project life cycle are needed. A-2000 PVC drainage pipe offers all of the initial cost advantages associated with thermoplastic pipe when compared with RCP but without the performance limitations of HDPE

drainage pipe. There's no reason to compromise on performance—**Select**

**A-2000 PVC: The Best Storm Sewer and Drainage Pipe on the Planet.**



Contech's A-2000 is lightweight and easy to handle.

# Best Pipe on the Planet



# Additional A-2000 Products and Applications

## A-2000 for Roof Drainage Systems

Managing large volumes of stormwater runoff from roof areas of industrial, commercial and warehouse facilities is more demanding than for most gravity-fed sewer systems. Additionally, intense rainfalls, combined with added building height, can create hydrostatic pressures within the pipe as well as on the joints and other system components. To handle these requirements, you need the higher strength and joint tightness of A-2000 PVC drainage pipe. Contech's full line of readily-available adapters and fittings makes connecting downspouts and laterals simple. Because of the unique gasket and bell design, there is no field beveling required.



## A2™ Liner Pipe for Trenchless Rehabilitation

Renew the performance of your aging underground infrastructure with A2 Liner Pipe—the proven, trenchless solution to sliplining existing sewers and culverts. Using the double wall A-2000 design, Contech developed A2 Liner Pipe for sliplining deteriorating pipelines where open trenching is not practical or desirable. You can install A2 Liner Pipe in diameters ranging from 12"-36" and in lengths from 2.5' to 20'—speeding installation. And because of its light weight, you can use smaller, less expensive equipment for installation—reducing costs.



## A-2000 Perforated Pipe for Subdrainage Systems

Contech A-2000 offers several critical features and benefits that make it the performance choice for subsurface drainage systems:

- 46 psi pipe stiffness for structural stability and improved deflection control.
- Glossy smooth interior for improved hydraulic capacity.
- PVC rigidity that provides essential beam strength for improved line and grade control during installation.
- Positive-gasketed jointing system.

Standard perforations for 4"-18" diameters are slots, while perforations for pipe sizes 21"-36" are circular  $\frac{3}{8}$ " diameter (.375") holes. Fully perforated A-2000 is also available for even greater open area.

Perforation Dimensions			
Pipe Size (in)	Slot Dimension/Hole Size (in) (min)	Centers (in)	Perforation Open Area (in <sup>2</sup> /LF)
4	1.062L x 0.031W	0.42	1.90
6	1.375L x 0.031W	0.52	1.98
8	1.750L x 0.031W	0.69	1.90
10	2.187L x 0.031W	8.83	1.98
12	1.687L x 0.051W	1.03	2.00
15	1.250L x 0.051W	1.38	2.00
18	2.250L x 0.051W	1.38	2.00
21	0.375 Diameter	1.60	3.30
24	0.375 Diameter	1.90	2.70
30	0.375 Diameter	2.32	2.20
36	0.375 Diameter	2.61	2.00



# Specifications

## Constant Stiffness Thermoplastic Pipe

**1.0 PIPE:** Polyvinyl Chloride (PVC) storm sewer/drain pipe and fittings shall be manufactured and tested in accordance with ASTM F949.

**2.0 MATERIAL AND DESIGN:** The structural design of thermoplastic pipes shall be in accordance with AASHTO LRFD titled: "Buried Structures and Tunnel Liners." To ensure long-term design strength properties, PVC pipe shall be manufactured from 12454 cell class material per ASTM D1784. Pipe and fittings shall have a minimum pipe stiffness of 46 lbs./in./in., when tested in accordance with ASTM D2412.

**3.0 JOINING SYSTEM:** Joints shall be an integral bell-gasketed joint. When the joint is assembled, it shall prevent misalignment of adjacent pipes and form either a soil tight joint (2 psi hydrostatic test per AASHTO Standard Specification for Highway Bridges) or a watertight joint (10.8 psi test per ASTM D3212 titled: "Standard Specification for Joints for Drain and Sewer Plastic Pipes using Flexible Elastomeric Seals") as required.

**4.0 HYDRAULICS CAPACITY:** The PVC Pipe covered in this section shall provide a Manning's "n" value of .009.

**5.0 INSTALLATION:** Thermoplastic pipe and fittings shall be installed in strict accordance with AASHTO Thermoplastic Specifications.

Contech Engineered Solutions LLC is a leading provider of site solution products and services for the civil engineering industry. Contech's product portfolio includes bridges, drainage, retaining walls, sanitary sewer, stormwater, erosion control, soil stabilization and wastewater products.

**For more information, call one of Contech's Regional Offices located in the following cities:**

<b>Ohio (Corporate Office)</b>	<b>513-645-7000</b>
Colorado (Denver)	720-587-2700
Florida (Tampa)	727-544-8811
Maine (Scarborough)	207-885-9830
Maryland (Baltimore)	410-740-8490
Oregon (Portland)	503-258-3180
Texas (Dallas)	972-590-2000

Visit our web site: [www.ContechES.com](http://www.ContechES.com)  
800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS AN EXPRESSED WARRANTY OR AN IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. SEE THE CONTECH STANDARD CONDITION OF SALES (VIEWABLE AT [WWW.CONTECHES.COM/COS](http://WWW.CONTECHES.COM/COS)) FOR MORE INFORMATION.

We print our brochures entirely on Forest Stewardship Council certified paper. FSC certification ensures that the paper in our brochures contain fiber from well-managed and responsibly harvested forests that meet strict environmental and socioeconomic standards.

FSC

Printed with soy inks

**Appendix B**

**“Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas”,**

**Guy Fipps, and Craig Pope**

**“Report 316 Evaluation of Ground-Water Resources in the Lower Rio Grande Valley”, by the Texas Water Development Board, 1990**



## **Irrigation District Efficiencies and Potential Water Savings in the Lower Rio Grande Valley of Texas**

*Guy Fipps and Craig Pope<sup>1</sup>*

### **Abstract**

Agriculture holds about 90 percent of all the water rights in the Lower Rio Grande Valley. Rapidly growing municipalities and industries are focusing the need to free up water for transfer from agriculture. This paper will give the results of an analysis of the 28 irrigation districts including their current efficiencies and opportunities for water savings. The analysis is based on reported efficiencies of each district, GIS-based maps and databases of district infrastructure, measurement of canal seepage losses, accounting systems, etc. Preliminary analysis indicate a potential water savings of 54,000 to 223,000 ac-ft/yr could result from improvements in the conveyance efficiency of 28 districts through renovations such as canal lining and pipeline replacement. Implementing a combination of on-farm practices of metering, gated pipe water delivery, and improved water management and/or technology could result in a water savings of between 98,000 and 217,000 ac-ft/yr.

### **Background**

The Lower Rio Grande Valley in Texas is located at the south most tip of the state at the end of the Rio Grande River. About 98% of all the water used in the Lower Rio Grande Valley, in both Texas and Mexico, is from the Rio Grande River. The region is undergoing rapid population and industrial growth. The Texas Water Development Board projects that by the year 2050, the population in the Valley will more than double, and municipal and industrial water demand will increase by 171% and 48%, respectively.

The lower Rio Grande River is over appropriated; that is, there are more water right permits than firm yield. Agriculture holds about 90% of the water rights and, depending on the year, accounts for about 80% of total withdrawals from the river. Thus, water to meet future demand will likely come from agriculture. The purpose of this study is to determine how much water could be "freed-up" by making improvement in the irrigation systems of the region.

In 1998, the area conducted an Integrated Water Resources Planning (IWRP) effort to identify water needs and sources over the 50 year period 2000 - 2050. This paper summarizes the portion of the project that examined potential water savings in irrigation districts and on-farm irrigation.

### **Description of the Irrigation Districts**

This study examines 28 water districts in Hidalgo, Cameron and Willacy Counties. These districts hold authorized agricultural water rights totaling 1,468,314 ac-ft (Table 1). Based on water rights holdings, the districts vary greatly in size, with the smallest district having 625 ac-ft of water rights and the largest district 174,776 ac-ft. Generally, these districts classify their water distribution networks into two categories: the "mains" and "laterals." The total miles of canals, pipeline and resacas comprising the main irrigation water distribution networks are summarized in Tables 2 and 3. Table 2 lists the total miles of the main canals by size (based on top width) and lining status. Table 3 provides the overall summary the extent of the main distribution networks which include 641.9 miles of canals, 9.7 miles of pipelines, and 44.6 miles of resacas.

### **Seepage and Conveyance Losses**



We conducted a review of the scientific literature on canal seepage losses and improvements in district efficiencies from rehabilitation projects. We only found a few articles that reported seepage rates for different lining materials and soil types. Seepage rates from these studies are summarized in Tables 4 and 5. Table 5 is of particular interest and gives seepage rates measured in five irrigation districts in South Texas, including the United and San Benito Irrigation Districts. Details of the literature search will be given in a later report.

We measured seepage losses in five canals and one pipeline network using the ponding method. This testing was conducted in and with assistance from four districts. The results of the ponding tests are summarized in Table 6. The three lined canals had very high seepage loss rates compared to the scientific literature, indicating problems with their construction or maintenance. The seepage rates of the two unlined canals fell in the ranges reported in the scientific literature. The pipeline network measurements took place in the Brownsville Irrigation District and showed very little seepage during the 24 hour test.

The term *conveyance efficiency* (or *water duty*) is a measurement of all the losses in an irrigation distribution system from the river (or diversion point) to the field. Conveyance efficiency is calculated from the total amount of water diverted in order to supply a specific amount of water to a field (usually 6 inches). Conveyance efficiency is expressed as efficiency, the percent of water lost, or amount of water pumped (in feet). For example, District A must pump 8 inches from the river in order to deliver 6 inches to the field. District A's losses can be expressed as a:

- conveyance efficiency of 75%,
- water duty of 25%, or
- water duty of 0.67 ft.

Table 1. The official and common names of 28 irrigation and water supply districts in the Lower Rio Grande Valley and their authorized agricultural water rights.		
Official Name	Common Name	Authorized Water Right (ac-ft)
Adams Gardens Irrigation District No. 19	Adams Garden	18,737
Bayview Irrigation District No. 11	Bayview	17,978
Brownsville Irrigation and Drainage District No. 5	Brownsville	34,876
Cameron County Irrigation District No. 3	La Feria	75,626
Cameron County Irrigation District No. 4	Santa Maria	10,182
Cameron County Irrigation District No. 6	Los Fresnos	52,142
Cameron County Water Improvement District No. 10	Rutherford-Harding	10,213
Cameron County Water Improvement	Cameron	3,913



District No. 16	#16	
Cameron County Water Improvement District No. 17	Cameron #17	625
Cameron County Water Improvement District No. 2	San Benito	151,941
Delta Lake Irrigation District	Delta Lake	174,776
Donna Irrigation District Hidalgo County No. 1	Donna	94,063
Engleman Irrigation District	Engleman	20,031
Harlingen Irrigation District No. 1	Harlingen	98,233
Hidalgo and Cameron Counties Irrigation District No. 9	Mercedes	177,151
Hidalgo County Improvement District No. 19	Sharyland	11,777
Hidalgo County Irrigation District No. 1	Edinburg	85,615
Hidalgo County Irrigation District No. 2	San Juan	147,675
Hidalgo County Water Irrigation District No. 3	McAllen #3	9,752
Hidalgo County Irrigation District No. 5	Progreso	14,234
Hidalgo County Irrigation District No. 6	Mission #6	42,545
Hidalgo County Irrigation District No. 16	Mission #16	30,749
Hidalgo County Irrigation District No. 13	Baptist Seminary	4,856
Hidalgo County Water Control and Irrigation District No. 18	Monte Grande	5,505
Hidalgo County Municipal Utility District No. 1	MUD	1,120
Santa Cruz Irrigation District No. 15	Santa Cruz	82,008
United Irrigation District of Hidalgo County	United	69,491
Valley Acres Water District	Valley Acres	22,500
		TOTAL 1,468,314

Table 2. Canal sizes and lining material for the main irrigation water distribution networks.

Top Width (feet)	Canal Type (or lining material, miles)	
	concrete	earth
< 10	41.6	1.0
10 - 20	98.0	11.9
20 - 30	25.2	52.2
30 - 40	3.8	35.1
40 - 50	1.1	60.1
50 - 75	1.4	30.9
75 - 100	0	11.1
> 100	0	9.7
<b>Unknown Widths</b>	99	134.5
<b>Total Miles</b>	270.1	346.4

Table 3. Miles of canals, pipelines and resacas for the main irrigation water distribution networks as shown on the Regional GIS Map (Fig. 1).

canals (miles)	pipelines (miles)	resacas (miles)	unknown (miles)	total (miles)
641.9	9.7	44.6	0.1	696.3

Conveyance loss includes a number of factors besides seepage and evaporation. Table 7 shows my classification system for conveyance losses which is composed of Transportation, Accounting, and Operational losses. The conveyance efficiencies as reported to us by 19 districts are listed in Table 8. The remaining 9 districts did not respond to survey and telephone requests for this information. The highest efficiencies are reported in smaller districts with extensive pipeline systems, while the lowest efficiencies are in larger districts which have undergone little rehabilitation. It should be pointed out that most districts do not have good data on their current conveyance efficiencies, and more work is needed to quantify these losses in order to target renovation programs.

We looked at the difference between the existing conveyance efficiencies and the efficiencies that which could reasonably be achieved by the districts through renovation projects. For the present analysis, we assumed that an efficiency of 80 to 90% was obtainable for most districts. Starting with the conveyance efficiency estimates provided by the 19 districts (Table 8), we calculated the potential water savings if all districts were brought up to 80 and 90% conveyance efficiency. For the 9 districts not reporting efficiencies, we assumed a present value of 75%. **The total potential water savings from conveyance efficiency improvement for all districts is 54,000 to 223,000 ac-ft/yr.**

Water saving potentials were computed for low water use years and high water use years. A low water use year is defined as diversion of 35% of the authorized water right and a high water use year as 80%. Since water-short districts use a higher percentage of their water rights, 45 and 90% were used for low and high water use years, respectively. These portions are based on an analysis of water diversions by each district during the period 1989 - 1997.



There is some question about the accuracy of the basic information used to estimate conveyance efficiency, particularly:

- 1) the amount of water pumped or diverted into the system, and
- 2) the actual amount of water delivered to the field.

The doppler flow meters currently used at many river pumping plants were "calibrated" for each site based on estimates of the current pumping rates and/or pumping plant capacity, and on engine/motor and pump performance. Due to the physical layout of the pumping plants, it is difficult to independently verify these rates. Likewise, little metering is done at the field turn-out, and the amount delivered is also an estimate in most districts.

Table 4. Canal seepage rates reported in published studies.	
Lining/Soil Type	Seepage Rate (gal/ft <sup>2</sup> /day)
plastic	0.08 - 3.74
concrete	0.06 - 3.22
gunite	0.06 - 0.94
compacted earth	0.07 - 0.6
clay	0.37 - 2.99
loam	4.49 - 7.48
sand	9.34 - 19.45

Sources: Bureau of Reclamation (1963); Nofziger, D.L. 1979. The influence of canal seepage on groundwater in Lugert Lake irrigation area. Oklahoma Water Resources Research Institute, OSU.

Table 5. Canal seepage rates reported in the Lower Rio Grande Valley.	
Soil Type	Seepage Loss Rate (gal/ft <sup>2</sup> /day)
clay	1.5
silty clay loam	2.24
clay loam	2.99
silt loam earth	4.49
loam	7.48
fine sandy loam	9.35
sandy loam	11.22

Source: Texas Board of Water Engineers. 1946. Seepage Losses from Canals in Texas, Austin. July 1.

Table 6. Seepage rates measured by the DMS Team in 5 irrigation canals in

the Lower Rio Grande Valley.

Test #	Canal Type	Top Width (ft)	Length (ft)	Seepage Rate (gal/ft <sup>2</sup> /day)	Total Loss in Canal (ac-ft/mile)	
					per day	per year*
1	concrete	19	2557	4.28	0.81	243
2	earth (clay)	38	3342	1.62	0.82	246
3	earth (sandy clay loam)	45	6336	1.69	1.05	315
4	concrete	12	2583	2.12	0.20	60
5	concrete	12.5	9525	2.49	0.25	75

\*based on 300 days per year.

Table 7. Classification of the sources of water loss in irrigation districts.

Transportation	Accounting	Operation
seepage in main, unlined canals	accuracy of field-level deliveries (estimates of canal riders/irrigators)	charging empty pipelines and canals
seepage in secondary territory unlined canals (laterals)	unauthorized use	spills (end of canals)
leakage from lined canals	metering at main pumping plant	partial use of water in dead-end lines
leakage from pipelines	water rights accounting system	
evaporation (canals and storage reservoirs)		

Table 8. Estimated conveyance efficiency as supplied by 19 districts.

District	Conveyance Efficiency (%)	District	Efficiency (%)
Adams Garden	85	HCMUD	90
Bayview	85	HCWID#3 (McAllen)	90
Brownsville	90	HCWID#5 (Progresso)	92



CCID#2 (San Benito)	40	HCCID#9 (Mercedes)	75
CCID#6 (Los Fresnos)	60	HCID#16 (Mission)	85
Delta Lake	75	HCWCID#18	95
Donna	58	La Feria IDCC#3	75
Harlingen	85	Santa Cruz ID#15	75
HCID#1 (Edinburg)	80	Santa Maria IDCC#4	75
HCID#2 (San Juan)	77		

### On-farm Potential Water Savings

On-farm irrigation efficiency is defined as the ratio of the amount of water needed to grow the crop to the amount of water delivered to a field. The amount of water needed to grow a crop is usually estimated from ET (evapotranspiration) data as adjusted for beneficial rainfall and leaching requirements. Generally, surface irrigation systems, such as found in the Lower Rio Grande Valley, have low efficiencies and ranges from 30 to 80%. Generally, we expect on-farm surface irrigation efficiencies of 60 - 70%. Various practices and field improvements can increase this efficiency to 70 - 80%, or even higher with good management and improved technology.

Table 9 provides the observed water savings reported in 4 districts (Bayview, Brownsville, Delta Lakes, San Benito) from recent experiments with layflat tubing replacement of siphon tubes and on-farm metering. In some cases, improved technology or water management were also implemented. The numbers reported for Donna and La Feria are for metering only. It should be noted that hard data to support many of these observations do not exist.

These observations and supporting information show that significant water savings at the farm level are possible in the Lower Rio Grande Valley. However, one major limiting factor is that in about half of the area, water is delivered to the field with inadequate "head" (insufficient volume and/or pressure) to allow for efficient furrow irrigation. Without improvements in the distribution systems, on-farm water saving potential in about half the irrigated land will be limited.

For the analysis used in the IWRP project, we classified potential on-farm water savings into three components:

- 1) metering,
- 2) gated pipe replacement of field ditches and siphon tubes, and
- 3) high water management and/or improved irrigation technology.

Table 10 gives the expected range of water savings for each practice and the factor used in this analysis. Table 11 summarizes the assumptions used in applying these factors to this region. For example, the first two factors (metering and gated pipe) were not applied to the area currently under the practice. In addition, benefits from high water management were not applied to the half of the area with head problems. Increased on-farm efficiency can only be achieved in these areas by improvements in the distribution systems and/or adoption of pumped and pressurized irrigation systems such as drip and sprinkler irrigation.

On-farm water saving potential were calculated for high and low water use years as discussed above. **The results are a potential on-farm water savings of 98,000 to 217,000 ac-ft/yr.** However, an intensive technical assistance and education program would be needed to achieve such savings.

Table 9. Water savings observed or estimated from metering and poly pipe experiments during the 1990s in the Lower Rio Grande Valley.

district	water savings observed
Bayview	36% <sup>1</sup>
Brownsville	33% <sup>1</sup>
Donna	20% <sup>2</sup>
La Feria	10% <sup>2</sup>
Delta Lakes	33% <sup>1</sup>
San Benito	40% <sup>1</sup>

<sup>1</sup> may include additional benefits from implementing improved on-farm water management practices or due to changes in irrigation technology

<sup>2</sup> metering only

Table 10. Factors used for calculation of on-farm water saving potential in the IWRP Project.

technique	expected water savings	factor used
metering	0 - 15 %	10 %
poly/gated pipe replacement of field ditches/siphon tubes	5 - 20 %	10 %
high management/improved irrigation technology	10 - 30 %	20 %

Table 11. Assumptions for applying water savings factors in Table 16 to the Lower Rio Grande Valley.

technique	assumptions for calculations
metering	- adopted Valley-wide by 2010 - 20% of land area is assumed to be metering - factor applied to remaining 80%
poly/gated pipe	- adopted by 90% of Valley by 2010 - approximately 50% of Valley already using gated/poly pipe - factor applied to remaining 40% of Valley not currently using poly/gated pipe (0.9 - 0.5 = 0.4)
	- adopted on half of Valley by 2010 - approximately 20% of area currently



high management/improved irrigation technology	under high management or using improved technologies - factor applied to 30% of area (0.5 - 0.2 = 0.3)
--	---

<sup>1</sup> Professor and Extension Agricultural Engineer, and Graduate Research Assistant, Department of Agricultural Engineering, Texas A&M University, College Station, TX 77843-2117.



**Texas Water Development Board**

**Report 316**

**Evaluation of  
Ground-Water Resources  
In the  
Lower Rio Grande Valley, Texas**

by  
**T. Wesley McCoy, Geologist**

**January 1990**



**Appendix C**  
**USDA Soil Survey for Cameron County**

SOIL SURVEY OF  
**Cameron County, Texas**



**United States Department of Agriculture**  
**Soil Conservation Service**  
In cooperation with  
**Texas Agricultural Experiment Station**



## **Appendix D**

**“Gulf Coast Jaguarundi Recovery Plan, First Revision,” U.S  
Fish and Wildlife Service; December, 2013**

**“Ocelot Recovery Plan, Draft First Revision”, U.S Fish and  
Wildlife Service Sothern Region; August, 1990**

**USFWS List of Endangered Species in Texas**

# GULF COAST JAGUARUNDI RECOVERY PLAN (*Puma yagouaroundi cacomitli*)

FIRST REVISION  
Original version part of  
Listed Cats of Texas and Arizona, 1990




Photo Credit: Feline Research Center/CKWRI

Southwest Region  
U.S. Fish and Wildlife Service  
Albuquerque, New Mexico  
December 2013

Approved: \_\_\_\_\_

*Joy E. Nudo*  
Regional Director, Region 2,  
U.S. Fish and Wildlife Service

Date: \_\_\_\_\_

*12/20/13*

**ACTING**



# **OCELOT RECOVERY PLAN**

*(Leopardus pardalis)*

**DRAFT FIRST REVISION**

**Original Approval: August 22, 1990**

**Southwest Region  
U.S. Fish and Wildlife Service  
Albuquerque, New Mexico**



U.S. Fish & Wildlife Service

## ECOS

[ECOS](#) / [Species Reports](#) / [Species occurrence by state](#)  
/ Listed species believed to or known to occur in Texas

# Listed species believed to or known to occur in Texas

## Notes:

- As of 02/13/2015 the data in this report has been updated to use a different set of information. Results are based on where the species is believed to or known to occur. The FWS feels utilizing this data set is a better representation of species occurrence. Note: there may be other federally listed species that are not currently known or expected to occur in this state but are covered by the ESA wherever they are found; Thus if new surveys detected them in this state they are still covered by the ESA. The FWS is using the best information available on this date to generate this list.
- This report shows listed species or populations believed to or known to occur in Texas
- This list does not include experimental populations and similarity of appearance listings.
- This list includes species or populations under the sole jurisdiction of the National Marine Fisheries Service.
- Click on the highlighted scientific names below to view a Species Profile for each listing.

## Listed species -- 99 listings

Animals – 69 listings

<b><u>Status</u></b>	<b><u>Species/Listing Name</u></b>
E	Amphipod, diminutive ( <a href="#">Gammarus hyalleloides</a> )
E	Amphipod, Peck's cave ( <a href="#">Stygobromus (=Stygonectes) pecki</a> )
E	Amphipod, Pecos ( <a href="#">Gammarus pecos</a> )
E	Bat, Mexican long-nosed Entire ( <a href="#">Leptonycteris nivalis</a> )



T	Bear, Louisiana black Entire ( <u><i>Ursus americanus luteolus</i></u> )
E	Beetle, American burying Entire ( <u><i>Nicrophorus americanus</i></u> )
E	Beetle, Coffin Cave mold Entire ( <u><i>Batrisodes texanus</i></u> )
E	Beetle, Comal Springs dryopid ( <u><i>Stygoparnus comalensis</i></u> )
E	Beetle, Comal Springs riffle ( <u><i>Heterelmis comalensis</i></u> )
E	Beetle, Helotes mold ( <u><i>Batrisodes venyivi</i></u> )
E	Beetle, Kretschmarr Cave mold Entire ( <u><i>Texamaurops reddelli</i></u> )
E	Beetle, [no common name] ( <u><i>Rhadine exilis</i></u> )
E	Beetle, [no common name] ( <u><i>Rhadine infernalis</i></u> )
E	Beetle, Tooth Cave ground Entire ( <u><i>Rhadine persephone</i></u> )
E	Crane, whooping except where EXPN ( <u><i>Grus americana</i></u> )
T	Cuckoo, yellow-billed Western U.S. DPS ( <u><i>Coccyzus americanus</i></u> )
E	Curlew, Eskimo Entire ( <u><i>Numenius borealis</i></u> )
E	Darter, fountain Entire ( <u><i>Etheostoma fonticola</i></u> )
E	falcon, northern aplomado Entire, except where listed as an experimental population ( <u><i>Falco femoralis septentrionalis</i></u> )
E	Flycatcher, southwestern willow Entire ( <u><i>Empidonax traillii extimus</i></u> )
E	Gambusia, Big Bend Entire ( <u><i>Gambusia gaigei</i></u> )
E	Gambusia, Clear Creek Entire ( <u><i>Gambusia heterochir</i></u> )
E	Gambusia, Pecos Entire ( <u><i>Gambusia nobilis</i></u> )
E	Harvestman, Bee Creek Cave Entire ( <u><i>Texella reddelli</i></u> )
E	Harvestman, Bone Cave Entire ( <u><i>Texella reyesi</i></u> )
E	Harvestman, Cokendolpher Cave ( <u><i>Texella cokendolpheri</i></u> )

E	Jaguarundi, Gulf Coast Wherever found ( <u><i>Herpailurus (=Felis) yagouaroundi cacomitli</i></u> )
T	Knot, red ( <u><i>Calidris canutus rufa</i></u> )
E	Manatee, West Indian Entire ( <u><i>Trichechus manatus</i></u> )
E	Meshweaver, Braken Bat Cave ( <u><i>Cicurina venii</i></u> )
E	Meshweaver, Government Canyon Bat Cave ( <u><i>Cicurina vespera</i></u> )
E	Meshweaver, Madla's Cave ( <u><i>Cicurina madla</i></u> )
E	Meshweaver, Robber Baron Cave ( <u><i>Cicurina baronia</i></u> )
T	Minnow, Devils River Entire ( <u><i>Dionda diaboli</i></u> )
E	Ocelot wherever found ( <u><i>Leopardus (=Felis) pardalis</i></u> )
T	Owl, Mexican spotted Entire ( <u><i>Strix occidentalis lucida</i></u> )
T	Plover, piping except Great Lakes watershed ( <u><i>Charadrius melodus</i></u> )
E	Prairie-chicken, Attwater's greater Entire ( <u><i>Tympanuchus cupido attwateri</i></u> )
T	Prairie-chicken, lesser ( <u><i>Tympanuchus pallidicinctus</i></u> )
E	Pseudoscorpion, Tooth Cave Entire ( <u><i>Tartarocreagris texana</i></u> )
E	Pupfish, Comanche Springs Entire ( <u><i>Cyprinodon elegans</i></u> )
E	Pupfish, Leon Springs Entire ( <u><i>Cyprinodon bovinus</i></u> )
E	Salamander, Austin blind ( <u><i>Eurycea waterlooensis</i></u> )
E	Salamander, Barton Springs Entire ( <u><i>Eurycea sosorum</i></u> )
T	Salamander, Georgetown ( <u><i>Eurycea naufragia</i></u> )
T	Salamander, Jollyville Plateau ( <u><i>Eurycea tonkawae</i></u> )
T	Salamander, Salado ( <u><i>Eurycea chisholmensis</i></u> )
T	Salamander, San Marcos Entire ( <u><i>Eurycea nana</i></u> )
E	Salamander, Texas blind Entire ( <u><i>Typhlomolge rathbuni</i></u> )



T	Sea turtle, green Except where endangered ( <i>Chelonia mydas</i> )
E	Sea turtle, hawksbill Entire ( <i>Eretmochelys imbricata</i> )
E	Sea turtle, Kemp's ridley Entire ( <i>Lepidochelys kempii</i> )
E	Sea turtle, leatherback Entire ( <i>Dermochelys coriacea</i> )
T	Sea turtle, loggerhead Northwest Atlantic Ocean DPS ( <i>Caretta caretta</i> )
T	Shiner, Arkansas River Arkansas R. Basin ( <i>Notropis girardi</i> )
E	Shiner, sharpnose ( <i>Notropis oxyrhynchus</i> )
E	Shiner, smalleye ( <i>Notropis buccula</i> )
E	Snail, Pecos assiminea ( <i>Assiminea pecos</i> )
E	Spider, Government Canyon Bat Cave ( <i>Neoleptoneta microps</i> )
E	Spider, Tooth Cave Entire ( <i>Neoleptoneta myopica</i> )
E	Springsnail, Phantom ( <i>Pyrgulopsis texana</i> )
E	Terrestrial, least interior pop. ( <i>Sterna antillarum</i> )
E	Toad, Houston Entire ( <i>Bufo houstonensis</i> )
E	Tryonia, Diamond ( <i>Pseudotryonia adamantina</i> )
E	Tryonia, Gonzales ( <i>Tryonia circumstriata</i> (=stocktonensis))
E	Tryonia, Phantom ( <i>Tryonia cheatumi</i> )
E	Vireo, black-capped Entire ( <i>Vireo atricapilla</i> )
E	Warbler (=wood), golden-cheeked Entire ( <i>Dendroica chrysoparia</i> )
E	Woodpecker, red-cockaded Entire ( <i>Picoides borealis</i> )

## Plants -- 30 listings

<b>Status</b>	<b>Species/Listing Name</b>
E	Ambrosia, south Texas ( <i>Ambrosia cheiranthifolia</i> )

E	Ayenia, Texas ( <u><i>Ayenia limitaris</i></u> )
E	Bladderpod, white ( <u><i>Lesquerella pallida</i></u> )
E	Bladderpod, Zapata ( <u><i>Lesquerella thamnophila</i></u> )
E	Cactus, black lace ( <u><i>Echinocereus reichenbachii</i> var. <i>albertii</i></u> )
T	Cactus, Chisos Mountain hedgehog ( <u><i>Echinocereus chisoensis</i> var. <i>chisoensis</i></u> )
T	Cactus, Lloyd's Mariposa ( <u><i>Echinomastus mariposensis</i></u> )
E	Cactus, Nellie cory ( <u><i>Coryphantha minima</i></u> )
E	Cactus, Sneed pincushion ( <u><i>Coryphantha sneedii</i> var. <i>sneedii</i></u> )
E	Cactus, star ( <u><i>Astrophytum asterias</i></u> )
E	cactus, Tobusch fishhook ( <u><i>Sclerocactus brevihamatus</i> ssp. <i>tobuschii</i></u> )
E	Cat's-eye, Terlingua Creek ( <u><i>Cryptantha crassipes</i></u> )
T	Cory cactus, bunched ( <u><i>Coryphantha ramillosa</i></u> )
E	Dawn-flower, Texas prairie ( <u><i>Hymenoxys texana</i></u> )
E	Dogweed, ashy ( <u><i>Thymophylla tephroleuca</i></u> )
E	Gladecress, Texas golden ( <u><i>Leavenworthia texana</i></u> )
E	Ladies'-tresses, Navasota ( <u><i>Spiranthes parksii</i></u> )
E	Manioc, Walker's ( <u><i>Manihot walkerae</i></u> )
T	No common name ( <u><i>Geocarpon minimum</i></u> )
T	Oak, Hinckley ( <u><i>Quercus hinckleyi</i></u> )
E	Phlox, Texas trailing ( <u><i>Phlox nivalis</i> ssp. <i>texensis</i></u> )
E	Pitaya, Davis' green ( <u><i>Echinocereus viridiflorus</i> var. <i>davisii</i></u> )
E	Pondweed, Little Aguja (=Creek) ( <u><i>Potamogeton clystocarpus</i></u> )



E	Poppy-mallow, Texas ( <i>Callirhoe scabriuscula</i> )
T	Rose-mallow, Neches River ( <i>Hibiscus dasycalyx</i> )
E	Rush-pea, slender ( <i>Hoffmannseggia tenella</i> )
E	Sand-verbena, large-fruited ( <i>Abronia macrocarpa</i> )
E	Snowbells, Texas ( <i>Styrax texanus</i> )
T	Sunflower, Pecos (=puzzle, =paradox) ( <i>Helianthus paradoxus</i> )
E	Wild-rice, Texas ( <i>Zizania texana</i> )

**Appendix E**  
**“Economic Impact Estimate of Irrigation Water shortage**  
**on the Lower Rio Grande Valley Agriculture”, Texas**  
**A&M University AgriLife Extension, June, 2013**



## Economic Impact Estimate of Irrigation Water Shortages on the Lower Rio Grande Valley Agriculture

Luis A. Ribera<sup>1</sup> and Dean McCorkle<sup>2</sup>  
<sup>1</sup>Associate Professor and Extension Economist  
<sup>2</sup>Extension Program Specialist  
 Texas A&M AgriLife Extension Service

The value of agricultural production in the Lower Rio Grande Valley (LRGV) region, which includes Cameron, Hidalgo, Starr and Willacy counties, was approximately \$820 million in 2012 (Table 1). Total crop production accounted for about \$666 million or 81.2 % of total agricultural production led by feed crops, cotton, vegetables, miscellaneous crops, and fruits and nuts. Livestock production and agricultural related production was \$67.5 and \$87.7 million, respectively.

**Table 1. Estimated Value of Agricultural Production for the LRGV, 2012**

	Cameron	Hidalgo	Starr	Willacy	Total LRGV
	(Thousands of Dollars)				
Feed Crops	52,639	66,410	5,718	53,392	178,159
Cotton	60,034	37,317	1,890	27,669	126,910
Oil Crops	374	9,836	2,342	0	12,552
Vegetable Crops	7,955	100,000	3,931	7,857	119,743
Fruits & Nuts	7,494	64,196	0	318	72,008
Sugar Cane	12,186	24,402	0	5,231	41,819
Misc. Crops	50,000	64,503	0	0	114,503
Beef	1,860	20,353	32,874	6,675	61,762
Other Meat Animals	0	5,550	58	31	5,639
Livestock Products	0	70	0	0	70
Ag. Related	51,454	31,200	3,400	1,682	87,736
<b>Total Crops</b>	<b>190,682</b>	<b>366,664</b>	<b>13,881</b>	<b>94,468</b>	<b>665,695</b>
<b>Total Livestock</b>	<b>1,860</b>	<b>25,973</b>	<b>32,932</b>	<b>6,706</b>	<b>67,471</b>
<b>Ag. Related</b>	<b>51,454</b>	<b>31,200</b>	<b>3,400</b>	<b>1,682</b>	<b>87,736</b>
<b>Total Agriculture</b>	<b>243,996</b>	<b>423,837</b>	<b>50,213</b>	<b>102,856</b>	<b>820,902</b>

Source: Estimated Value of Agricultural Production and Related Items, Texas AgriLife Extension Service, May 2013.

Irrigation water is very important to agricultural production in the LRGV region where about half of its crop production acreage is irrigated. Irrigation water shortages in the LRGV have occurred since the mid-1990s (Robinson, 2002). These shortages followed the point in 1992, when Mexico began undersupplying the average minimum annual amount of 350,000 acre-feet of water into the Rio Grande and continue nowadays. The treaty of 1944 requires Mexico to deliver the 350,000 minimum average annual acre-feet over the defined five-year cycles. The water deficit for the current five-year cycle is 430,000 acre-feet (TCEQ, 2013).

The purpose of this paper is to estimate the economic impact of the absence of irrigation water for crop production in the LRGV region. The crops affected by the absence of irrigation water are row crops (mainly sorghum, cotton and corn) and specialty crops (mainly vegetables, citrus and sugarcane). Row crops can be grown either irrigated or dryland while specialty crops can only be grown irrigated. All row crops and specialty crops are annual crops except for citrus and sugarcane. The lifespan of a citrus tree is over 30 years while sugarcane is typically five years. The methodology used in this study is an *ex post* historical crop damage approach where the economic impacts are estimated by measuring the change in farm gate or regional gross value of affected row crops and specialty crops.

### Row Crops

To estimate the impact of the lack of irrigation water in row crops, the difference between irrigated and dryland yields are estimated and multiplied by the irrigated acreage for the crop. To account for the year-to-year fluctuations in yields and crop acres, a 5-year average (2008-2012) of crop yields and acreage is used to project the impacts for 2013. For example, using the estimated cotton yield difference between irrigated and dryland production (488 lbs. per acre), the 5-year average irrigated cotton acres, and the 2013 estimated cotton price; the loss in farm-gate cotton revenue is estimated at \$12.5 million for 2013 (Table 2). Therefore, with the absence of water, irrigated row crops will produce dryland yields, causing a reduction in row crop farm-gate values of \$12.5, \$4.5 and \$14.1 million for cotton, corn and sorghum, respectively. The total farm-gate loss for row crops is estimated at \$31.2 million.

Table 2. Row Crop Losses due to Lack of Irrigation Water in the LRGV

	Yield <sup>1</sup>	Yield Loss <sup>1</sup>	Acreage <sup>2</sup>	2013 Price <sup>3</sup>	Total Farm Gate
	5-year average				
<b>Cotton</b>					
Irrigated	1,017 (lbs)	<b>-488 (lbs)</b>	32,273	\$0.80/lb	\$12,554,709
Dryland	528 (lbs)		76,572		
<b>Corn</b>					
Irrigated	99 (bu)	<b>-22 (bu)</b>	31,317	\$6.61/bu	\$4,533,345
Dryland	77 (bu)		8,034		
<b>Sorghum</b>					
Irrigated	77 (bu)	<b>-29 (bu)</b>	80,267	\$6.00/bu	\$14,134,952
Dryland	48 (bu)		284,450		
<b>Total Row Crop Loss</b>					<b>\$31,223,006</b>

<sup>1/</sup> USDA-NASS Quick Stats for LRGV region, 2008-2012.

<sup>2/</sup> USDA-FSA annual crop acreage report for LRGV region, 2008-2012.

<sup>3/</sup> CME Group Cotton, Corn and Sorghum July 2013 Prices.



## Specialty Crops

To estimate the impact of the lack of irrigation water in specialty crops, these crops were divided between perennial, i.e. citrus, and annual crops, i.e. vegetables and sugarcane. Citrus production would be close to zero, but in general, trees would survive a season without irrigation water. It is assumed that citrus orchards would not be turned into an annual crop since replacing mature trees is very expensive. Therefore, the economic loss of the lack of irrigation water at the farm-level would be the 5-year average value of citrus production in the LRGV region, \$45.82 million (Table 3). Vegetables and sugarcane production would be lost as well as irrigation water is needed for their production. Estimated economic loss at the farm-level would be the 5-year average value of production, \$128.21 and \$47.36 million for vegetable and sugarcane production, respectively (Table 3). The total value of specialty crop production is \$221.3 million.

**Table 3. Specialty Crop Acreage and Value of Production Loss**

	Acreage <sup>1</sup>	Value of Production <sup>2</sup>
	5-year average	
Citrus	27,038	\$45,822,200
Vegetables	29,303	\$128,211,200
Sugarcane	40,812	\$47,361,180
<b>Total Specialty Crop Loss</b>		<b>\$221,394,580</b>

<sup>1/</sup> USDA-FSA annual crop acreage report for LRGV region, 2008-2012.

<sup>2/</sup> Estimated Value of Agricultural Production and Related Items, Texas AgriLife Extension Service, May 2013.

However, it is improbable that the acreage used in vegetable and sugarcane production would remain out of crop production; instead they would be converted into dryland crop production, which for the LRGV region would most likely be cotton, corn or sorghum. The methodology used to redistribute this acreage includes the 5-year average crop mix in the LRGV region and using the same crop mix ratio to convert the vegetable and sugarcane acreage into row crops (Table 4). Therefore, 21% of the converted acreage would go into cotton, 8% into corn and 71% into sorghum production; accounting for \$23.39 million in production value at the farm-level. This value, \$23.39 million, is subtracted from the total loss of specialty crop production. Therefore, the total crop production loss due to the lack of irrigation water in the LRGV region is estimated at \$229.24 million, which includes row crop losses of \$31.22 million, plus the specialty crops losses of \$221.39 million, less the value of row crop production of the converted vegetable and sugarcane acreage, \$23.39 million.

**Table 4. Value of Production of Vegetables and Sugarcane Acreage Turned Into Row Crop Production**

	Crop Mix <sup>1</sup>	Acreage Mix	Yield <sup>2</sup>	Price <sup>3</sup>	Value
	5-year average		Dryland		
Cotton	21%	14,879	528	\$0.80	\$6,284,925
Corn	8%	5,379	77	\$6.61	\$2,737,867
Sorghum	71%	49,857	48	\$6.00	\$14,358,794
<b>Total Gross Revenue</b>					<b>\$23,381,586</b>

<sup>1/</sup> USDA-FSA annual crop acreage report for LRGV region, 2008-2012.

<sup>2/</sup> USDA-NASS Quick Stats for LRGV region, 2008-2012.

<sup>3/</sup> CME Group Cotton, Corn and Sorghum July 2013 Prices.

### **Total Economic Impact**

The IMPLAN input-output model was used to assess the broader economic effects associated with the estimated \$229.24 million crop revenue loss associated with a loss of irrigation water. These effects are measured via three indicators – employment, value added, and economic output. Employment represents both full and part-time jobs, value added is a measure of net business income and employee compensation, and economic output represents gross business activity (spending) associated with irrigated crop production. Value added also represents a contribution to Texas’ Gross Domestic Product (GDP), the most commonly used indicator of the health of the state’s economy.

Each of these indicators is measured at three different levels: direct effects represent the farm-level effects; indirect effects represent effects in industries that provide input supplies (fertilizer, fuel, etc.) to farms, and induced effects represent the economic impacts associated with the spending of salaries and wages on household goods. The loss of irrigated crop production in the LRGV region would lead to an estimated \$394.9 million loss in economic output (Table 5). Likewise, the loss of irrigated crop production in the LRGV region would generate a loss of \$217.61 million in value added. In terms of employment, the loss of irrigation would result in an estimated loss of 4,840 jobs that depend on the production and sales of these commodities for some portion of their income.

**Table 5. 2013 Projected Economic Losses Associated with Lack of Irrigation Water in the LRGV**

Impact Type	Employment	Total Value Added	Output
Direct Effect	3,041.6	\$117,175,997	\$229,235,999
Indirect Effect	1,292.2	\$66,615,832	\$109,530,397
Induced Effect	506.3	\$33,820,341	\$56,130,084
<b>Total Effect</b>	<b>4,840.1</b>	<b>\$217,612,170</b>	<b>\$394,896,481</b>



Value added and economic output are two distinct indicators, and as such are not to be added together.

This analysis represents the impacts of all economic activities that occur in the production of the described crops, up until the point of sale of the crops at the farm-level. These results are on the conservative side as they do not include the impacts (losses) that occur beyond the farm-level sale of the crops, such as transportation, storage, processing, packaging, and marketing.

### **References**

Minnesota IMPLAN Group, Inc., 2009, IMPLAN System, 502 2<sup>nd</sup> St., Hudson, WI 54016 (Implan.com).

Robinson, John R.C. "Alternative Approaches to Estimate the Impact of Irrigation Water Shortages on Rio Grande Valley Agriculture." Texas Cooperative Extension, May 17, 2012.

[TCEQ] Texas Commission on Environmental Quality. "Rio Grande Valley Suffers While Mexico Withholds Water." News release, April 16, 2013. Available at: <http://www.tceq.texas.gov/news/releases/4-16waterdeficit>

**Appendix F**  
**CCID2 Water Conservation Plan and a Drought**  
**Contingency Plan**



**WATER CONSERVATION PLAN  
FOR THE  
CAMERON COUNTY IRRIGATION DISTRICT #2  
April 22, 2014**

In an effort to establish an Irrigation District where water is used efficiently and conservatively, Cameron County Irrigation District #2 sets forth the following water conservation plan.

Cameron County Irrigation District #2 currently has approximately 48,000 acres production, which include acreage for vegetables, cotton, grain, pasture, orchards, and sugar cane. Our total servicing area is approximately 110 square miles. Water is diverted from the Irrigation District's pumping plant facilities located on the United States side of the Rio Grande River at Los Indios, Texas. After pumping from the river, the water is then transported to two main canals one of, which provides water to the south side of the District, and the other to two reservoirs, which provide water to the north side of the District along with other resacas. All water travels north through open canals.

The District delivers approximately 10,611 acre-feet of Rio Grande water to the City of San Benito, East Rio Hondo Water Supply, City of Rio Hondo and Arroyo Water Supply Corporation under existing water supply and delivery contracts. This water is delivered from the District's irrigation canal and pipeline system and is metered at the delivery point to the City of San Benito, East Rio Hondo Water Supply, City of Rio Hondo and Arroyo Water Supply Corporation. The amount of water measured at the Rio Grande is reported monthly to the Rio Grande Watermaster and is based upon the amount of water delivered plus transportation losses. The Rio Grande Watermaster charges these deliveries against the applicable municipal priority water allocation.

In the future, water supply and delivery contracts entered into for the furnishing of Rio Grande water to municipal suppliers, or any extension of existing contract, shall contain provisions that the customer shall develop and implement a water conservation plan or water conservation measures using the applicable elements contained in Title 30, Texas Administrative Code, Chapter 288, and in the event, after treatment, such water is resold to another supplier, then such contract shall also contain provisions dealing with water conservation requirements in accordance with Title 30, Texas Administrative Code, Chapter 288.

A copy of this Water Conservation Plan shall be filed with the Rio Grande Regional Water Planning Group (Region M, Texas Water Development Board), or its successor, and the District will coordinate its activities in order to ensure consistency with approved Regional Water Plans.

### **Conservation Goals:**

1. Landowners and/or canal riders report all leaks to the District's office.
2. Water is shut off at the gate immediately after acreage has been irrigated to avoid spills.
3. No irrigation will begin until canal rider has been notified of intent to irrigate, conservation measures have been taken, and amount of acreage to be irrigated is specified for the control of quantity of water.
4. Land leveling is recommended for long term permanent reduction in irrigation water use.
5. Poly pipes are being installed to use water more effectively and efficiently.
6. District has sold water rights to begin to rehabilitate the District by putting canals underground into pipeline for conservation.

### **Monitoring and Record Management**

Cameron County Irrigation District #2 uses a canal rider supervisor to check the structural facilities for storage, conveyance and delivery of water. Canal riders monitor the water being used to account for the water paid in the amount of \$8.00 per acre. A copy of the order placed for water is provided to the canal rider who will turn the order back in when completed or with notification of cancellation of such order.

### **Penalties:**

Any person who willfully opens, closes, changes or interferes with any headgate or used water in violation of section 11.083 of the Texas Code may be assessed an administrative penalty up to \$5,000.00 a day under section 11.0842 of the Texas Water Code. Additionally, if the violator is also taking, diverting, or appropriating state water, the violator may be assessed a civil penalty in court of up to \$5,000.00 a day. Someone who is aggrieved by these violations may sue the violator for injunctive relief and civil damages in court.

### **Severability**

It is hereby declared to be the intention of the Board of Cameron County Irrigation District #2 that the sections paragraphs, sentences, clauses, and phrases of this Plan are severable and, if any phrase clause sentence, paragraph, or section of this Plan shall be declared unconstitutional by the judgment or decree of any court of competent jurisdiction, such unconstitutionality shall not affect any of the remaining phrases, clauses, sentences, paragraphs, and sections of this Plan since the same would not have been enacted by the Board of Cameron County Irrigation District #2 without the



incorporation into this Plan of any such unconstitutional phrase clause, sentence, paragraph, or section.

**Effective Date:**

The effective date of the above shall be immediately upon its passage. Resolution is attached to the water conservation plan.

**Appendix G**  
**Letters of Project Support**



## East Rio Hondo Water Supply Corporation

206 Industrial Pkwy. \* P.O. Box 621 \* Rio Hondo, Texas 78583 \* www.erhwsc.com \* Phone (956) 748-3633 Fax 748-3179

*"This institution is an equal opportunity provider and employer"*

March 4, 2019

Cameron County Irrigation District #2  
P. O. Box 687  
San Benito, TX 78586

Subject: Support of Proposed Piping of Lateral 8

Dear Mrs. Lambert,

This letter is in support of your WaterSMART application to the U.S. Bureau of Reclamation for granting funding of a water conservation initiative. As a rural water supplier in Cameron County Irrigation District #2's jurisdiction, East Rio Hondo Water Supply Corporation (ERHWSC) supports improving the efficiency of irrigation water delivery and reducing water loss by replacing open canals with pipelines. Any water conserved by the irrigation district directly benefits ERHWSC's future water supply and needs.

ERHWSC hereby supports your proposed efforts to pipe your existing earthen Lateral 8 as a water conservation effort.

Sincerely,



Brian E. Macmanus, P.E.  
General Manager

**Appendix H**  
**CCID2 Grant Application Board Resolution**



**CAMERON COUNTY IRRIGATION DISTRICT NO.  
TWO**

26041 FM 510 P.O. BOX 687 SAN BENITO, TEXAS 78586  
Phone (956) 399-2484 Fax (956) 399-4721  
**Sonia Lambert- General Manager**

**RESOLUTION**

March 14, 2019  
2019-006

**LATERAL 8**

from Gamble to Canal 8 Pipeline, Blk 59 SBL&WCO

APPLICANT'S NAME: Cameron County Irrigation District No. 2

**WHEREAS**, Cameron County Irrigation District No. 2 is an Irrigation District operating pursuant to Vernon's Texas Civil Statutes, Water Code, Chapter 58, and under Article XVI, Section 59, of the Texas Constitution; and

**WHEREAS**, the Cameron County Irrigation District No. 2, (District), is committed to water conservation, and;

**WHEREAS**, the District is seeking opportunities to implement projects that account for water use, and;


**WHEREAS**, Cameron County Irrigation District No. 2, San Benito, Texas, has identified a project that involves replacement of an open earthen canal to a pipeline.

**WHEREAS**, the District has sufficient resources to match available funds to complete such improvements;

**NOW THEREFORE, BE IT RESOLVED** that the Board of Directors of the Cameron County Irrigation District No. 2 agrees and authorizes that:

1. The Board authorizes its General Manager, Sonia Lambert, to submit an application for the WaterSMART Grant.
2. The Board or governing body has reviewed and supports the proposal submitted;
3. The applicant is capable of providing the amount of funding and/or in-kind contributions, specified in the funding plan; and
4. If selected, the applicant will work with Reclamation to meet established deadlines for entering into a cooperative agreement.

DATED: 3/14/19

  
\_\_\_\_\_  
Sam Simmons, President

ATTEST:

  
\_\_\_\_\_  
William Goad, Secretary

**Board of Directors**

Sam Simmons-President  
William Goad-Secretary

Brady Taubert-Vice President  
Buck Rhyner-Member

**Appendix I**  
**CCID2 Accounting Balance Sheet**





# FIRST COMMUNITY BANK

Other Banks Have Branches, We Have Roots.

Page: 1

Cameron County Irrigation Dist 2  
Canal Rehab Account  
PO Box 687  
San Benito, TX 78586-0007

### PERIODIC STATEMENT

Date: Feb 28, 2019  
Period: Feb 01, 2019 to  
Feb 28, 2019  
(28 Days )

Please visit our web site at [WWW.FCBWEB.NET](http://WWW.FCBWEB.NET)  
If you have any questions, please contact us at (956)399-3331.  
For 24 hour banking information, please call (888) 361-3661.

---

**ACCOUNT #: DDA - 0000036641    Public Now-Analysis**

Enclosures: 0

Beginning Balance	
as of 02/01/19	376,706.43
Deposits & Other Credits	361.23
Charges & Fees	0.00
Checks & Other Debits	0.00
Average Balance	376,706.43
<b>Ending Balance</b>	
as of 02/28/19	<b>377,067.66</b>

#### Transaction Information

Date	Check#	Description	Debit Amount	Credit Amount
02/28		Interest Credit		361.23

#### Daily Balance Information

Date	Balance	Date	Balance	Date	Balance
02/28	377,067.66				



# FIRST COMMUNITY BANK

Other Banks Have Branches, We Have Roots.

Cameron County Irrigation Dist 2  
Rehab-Account  
PO Box 687  
San Benito, TX 78586-0007

**PERIODIC STATEMENT**

Date: Feb 28, 2019  
Period: Feb 01, 2019 to  
Feb 28, 2019  
(28 Days )

Please visit our web site at WWW.FCBWEB.NET  
If you have any questions, please contact us at (956)399-3331.  
For 24 hour banking Information, please call (888) 361-3661.

**ACCOUNT #: DDA - 0000035378      Public Now-Analysis**

Enclosures: 0

Beginning Balance	
as of 02/01/19	4,465.53
Deposits & Other Credits	134,483.70
Charges & Fees	0.00
Checks & Other Debits	0.00
Average Balance	23,674.24
<b>Ending Balance</b>	
as of 02/28/19	<b>138,949.23</b>

**Transaction Information**

Date	Check#	Description	Debit Amount	Credit Amount
02/25		ACH Credit GRANT PAY ASAP ID9051036803 0001\REF*ZZ*15507\SE*13*00002 32\GE*1*0000232\IEA*1*0000002 32		134,461.00
02/28		Interest Credit		22.70

**Daily Balance Information**

Date	Balance	Date	Balance	Date	Balance
02/25	138,926.53	02/28	138,949.23		



# FIRST COMMUNITY BANK

Other Banks Have Branches, We Have Roots.

Page: 1

Cameron County Irrig Dist.2 Water 2025  
Metering Proj Automtc Gates 2nd  
PO Box 687  
San Benito, TX 78586-0007

### PERIODIC STATEMENT

Date: Feb 28, 2019  
Period: Feb 01, 2019 to  
Feb 28, 2019  
(28 Days )

Please visit our web site at WWW.FCBWEB.NET  
If you have any questions, please contact us at (956)399-3331.  
For 24 hour banking Information, please call (888) 361-3661.

**ACCOUNT #: DDA - 0000037222      Public Now-Analysis**

Enclosures: 5

Beginning Balance	
as of 02/01/19	486,209.02
Deposits & Other Credits	420.95
Charges & Fees	0.00
Checks & Other Debits	151,416.31
Average Balance	438,996.54
<b>Ending Balance</b>	
as of 02/28/19	<b>335,213.66</b>

#### Transaction Information

Date	Check#	Description	Debit Amount	Credit Amount
02/22		Tfr to XXXXXX6158 IN KIND TRF		
		JAN 2019 Cameron County Irrig	22,958.60	
02/28		Interest Credit		420.95

#### Check Information

Date	Check#	Amount	Date	Check#	Amount
02/20	1242	122,702.48	02/20	1245	134.96
02/21	1243	250.19	02/19	1246	4,474.08
02/19	1244	896.00			

#### Daily Balance Information

Date	Balance	Date	Balance	Date	Balance
02/19	480,838.94	02/20	358,001.50	02/21	357,751.31





Account #: DDA-0000037222

**PERIODIC STATEMENT**  
Cameron County  
Irrigation Dist 2

Feb 28, 2019

**Daily Balance Information (continued)**

Date	Balance		Date	Balance		Date	Balance
02/22	334,792.71		02/28	335,213.66			